

Quality Control Manual

For the PWD Standard Specification for Road and Bridge Works

Version 1

June 2018



Public Works Department, PMB 9044, Port Vila, Vanuatu

Document Owner:	Junior George, A/Director, Public Works Department

Group	Rev No.	Date	Revision Details	Author	Reviewer	Approver
	Final	6/6/18	First issue of Final document	VIRIP	PMC, VIRIP	A/Director PWD

Prologue

This Manual has been produced for the quality control of civil construction contracts in accordance with Public Works Department Standard Specification for Road and Bridge Works.

All works implemented in accordance with the PWD Standard Specifications must use this Manual to ensure compliance with the quality requirements, as outlined in this Specifications.

It is only through the systematic approach of site inspections and quality audits carried out during a construction project that PWD can be assured that the quality of the works is correct and the Government is achieving value for money.

Users of the Manual are invited to submit comments or to suggest changes. These should be directed to the Director Public Works Department, so that changes, if appropriate, may be incorporated into future revisions.

Junior Shim George

Acting Director

Contents

1		Pur	pose	of the Manual	4		
2		Introduction5					
	2	.1	Gen	eral	5		
		2.1.	1	Introduction	5		
	2	.2	Defi	nitions	5		
		2.2.	1	Quality Assurance	5		
		2.2.	2	Quality Control	5		
		2.2.	3	Inspection	5		
3		Con	tract	ual Background	6		
	3	.1	Star	ndard Forms of Conditions of Contract	6		
		3.1.	1	General	6		
		3.1.	2	Vanuatu Government Works Contract	6		
		3.1.	3	FIDIC	7		
	3	.2	The	Contract	9		
		3.2.	1	Contract Documents	9		
		3.2.	2	Employer's Technical Specifications (or Employer's Requirements)	9		
		3.2.	3	Cross Referencing 1	1		
	3	.3	The	Construction Supervisor1	1		
		3.3.	1	Authority 1	1		
		3.3.	2	Delegation1	1		
		3.3.	3	Site Inspection	1		
		3.3.	4	Contractor Notifications and Hold Points1	2		
		3.3.	5	Measurement1	2		
		3.3.	6	Records	3		
4		Qua	ality A	Assurance System	3		
	4	.1	Req	uirements1	3		
		4.1.	1	Contractor's Obligations	3		
		4.1.	2	Quality System Audit	3		
		4.1.	3	Testing Requirements	4		
	4	.2	Che	ck Sheets	5		
		4.2.	1	General1	5		
	4	.3	Usir	ng the Check Sheets1	5		
	4	.4	List	of Check Sheets	7		
					8		

APPENDIX A Forms for Contractor Notifications	144
APPENDIX B Site Record Forms	148
APPENDIX C - Guidance for Additional Sheets	153

1 Purpose of the Manual

The purpose of this manual is to provide guidance and check sheets to assist project supervisors in carrying out their duties in regard to ensuring that the Employer's Technical Requirements are met. It forms part of a Quality Assurance System

The use of this manual will help to ensure that a systematic approach has been introduced to the site inspections and quality audits carried out during a construction project and that supervisors are not just going to site to 'have a look around'.

The systematic approach is introduced by following the check sheets. Through the completion of all the relevant check sheets there can be a high level of confidence that all of the Employer's Requirements in the PWD Standard Specification for Road and Bridge Works have been fulfilled by the Contractor. When the Construction Supervisor or a delegate signs off on the form, he or she takes the responsibility for having witnessed the approved works and carried out the checking procedures.

The Check Sheets apply only to the requirements of the PWD Standard Specification and the additional requirements contained in any Supplementary Specification or an Environmental Management Plan will require additional sheets to be prepared at the outset of the contract under supervision

2 Introduction

2.1 General

2.1.1 Introduction

Although the two phrases Quality Control and Quality Assurance are often used interchangeably the difference is considered to be one of function

2.2 Definitions

2.2.1 Quality Assurance

Quality Assurance in the construction industry means an undertaking to follow a set of procedures and tests which will have a high degree of probability of providing work that complies with the specification.

2.2.2 Quality Control

Quality control is the inspection aspect of quality management.

2.2.3 Inspection

Inspection is the process of examining, measuring, and testing to assess one or more characteristics of a product in order to compare the results with the specified requirements and determine conformity.

3 Contractual Background

3.1 Standard Forms of Conditions of Contract

3.1.1 General

The Contract is a legally enforceable agreement which gives rise to various rights and obligations to the parties to the Contract.

The Conditions of Contract set out those rights and obligations in detail.

Standard Forms of Contract Conditions are commonly used for construction projects. They have developed over many years and incorporate lessons learnt from their application in practice. They are periodically updated by expert panels based on experience gained during use and feedback from users. A body of knowledge develops on how to implement the contract conditions, that has often been tested in law, and this contributes to efficient project management.

Construction projects are unique (no two projects are entirely identical) and often complicated by events that occur during the implementation. Problems often emerge caused by such matters as late issue of drawings, land access issues, survey errors, weather events, unexpected ground conditions, problems with relocating utilities, quality control issues, variations and late payment.

A good set of contract conditions will set out how the parties should respond to all such events.

The next two sections look very briefly at the Forms of Contract most likely to be used for the construction of public works in Vanuatu. The purpose is to demonstrate the Contractor's obligation under the Contract to carry out work according to the specified requirements and the derivation of the authority of site inspection personnel to issue instructions to the Contractor and to have improper work rectified.

3.1.2 Vanuatu Government Works Contract

The Central Tenders Board has developed a suite of standard forms for a range of procurement tasks, including one for construction works.

In the Works conditions, the two Parties to the Contract are described as the Employer and the Contractor. The Employer is responsible for providing the design, access to the Site and for making timely payments.

The Employer appoints the Construction Supervisor who "on behalf of the Employer, supervises the Construction and certifies the completion of the Works"

The Construction Supervisor is responsible for a range of administrative duties including amongst many other things to *"order the removal or the rectification of defects"*. The Construction Supervisor may delegate any or all of his powers to a Representative to carry out supervision at the Site.

The Contractor is responsible (clause 5.3.1) for performing the Works *"as specified in the Drawings and Specifications and the Contractor with due diligence and in a good*

workmanlike manner shall carry out and complete the Works to the reasonable satisfaction of the Construction Supervisor"

Under clause 5.6.1 "All materials used in the Works and the standards of workmanship shall conform to the provisions of the Contract" And

"If the Construction Supervisor is of the opinion that any materials or the work or any part thereof, whether fixed or not, is unsatisfactory he may direct its replacement, removal or correction at the Contractor's expense".

Under Clause 5.3.1 "The Contractor shall carry out all instructions of the Construction Supervisor which comply with the applicable laws of the Republic of Vanuatu".

The Contractor has a specific duty to "check and verify dimensions on Drawings on Site before proceeding with the Works, and bring any ambiguities in the Drawings and Specifications to the attention of the Construction Supervisor"

The Contractor appears to take the risk of ground conditions as he is "deemed to have satisfied himself as to the nature of the ground and the subsoil before submitting his tender"

3.1.3 FIDIC

The Fédération Internationale des Ingénieurs-Conseils ("FIDIC") issue what is commonly referred to as the 'rainbow' suite of contracts. This phrase comes about as each form of contract has a distinctively coloured jacket on the hard copy issue. Current FIDIC editions were issued in 1999.

The two Forms most likely to be used in Vanuatu Public Works Department are the Pink Book (full name "Multilateral Development Bank Harmonised Version of Conditions of Contract for Construction for Building and Engineering Works Designed by the Employer") and the Yellow book (Conditions of Contract for Plant and Design-Build for Electrical and Mechanical Plant and for Building and Engineering Works, Designed by the Contractor).

3.1.3.1 The Pink Book

The MDB Harmonised version (Pink Book) was released in 2005 but has been amended in 2006 and 2010. The Pink Book is an amended version of the FIDIC Red Book. It includes areas that provide some particular requirements of the funding agencies but also includes changes to some clauses of a more general nature.

Large sections of both Forms are identical. The differences are however pertinent and users familiar with one version should take care when using the other not to overlook the differences.

The use of the Pink Book is mandatory for all ADB and World Bank funded projects exceeding a specified cost threshold. (For VIRIP this threshold is US\$ 1.0 million).

FIDIC Pink Book is more suited to re-measure contracts or measure and value. This means that the Contractor has submitted his tender rates and prices based on estimated quantities set out in a Bill of Quantities. Actual payments are however based on the amount of work actually carried out in accordance with the Contract. The Pink Book can be used for a Lump Sum form of contract in which case a Schedules of Rates would replace the Bill of Quantities

but some amendments to the General Conditions would also be required by Special Conditions of Contract.

In FIDIC the two Parties to the Contract are described as the Employer and the Contractor. The Employer (under the Pink Book) is responsible for providing the design, access to the Site and for making timely payments. (Despite the general provisions of the Pink Book there can be circumstances in which the Employer provides some of the materials and the Contractor carries out some of the design).

The Employer appoints the Engineer whose duty is to administer the Contract and *"carry out the duties assigned to him under the Contract"* (Clause 3.1). This includes providing instructions and notices to the Contractor, checking the quality of the materials and workmanship, measuring and valuing the works carried out, issuing interim payment certificates, issuing the completion certificate and responding to claims for delay and/or additional payment.

The Engineer can under Clause 3.2 delegate authority to Assistants who may then act on the Engineer's behalf in carrying out duties within the ambit of the delegation. The authority to issue Determinations under clause 3.5 is not delegated unless a special provision is made in the Particular Conditions.

The Contractor is required under Clause 4.1 to "execute and complete the Works and remedy any defects therein in conformity with the provisions of the Contract" and to be responsible for "the adequacy, stability and safety of all Site operations and of all methods of construction".

Under clause 7.1

"The Contractor shall carry out the manufacture of Plant, the production and manufacture of Materials, and all other execution of the Works:

- (a) in the manner (if any) specified in the Contract,
- (b) in a proper workmanlike and careful manner, in accordance with recognised good practice, and
- (c) with properly equipped facilities and non-hazardous Materials, except as otherwise specified in the Contract".

Under Clause 3.3 "The Contractor shall only take instructions from the Engineer or from an assistant to whom the appropriate authority has been delegated"

3.1.3.2 The FIDIC Yellow book

The Conditions of Contract for Plant and Design-Build for Electrical and Mechanical Plant and for Building and Engineering Works, Designed by the Contractor (the Yellow Book) is often used for projects where the Contractor is to be responsible for the design of the works as well as construction. The Contractor has an obligation to design, execute and complete the Works in accordance with the Contract but in addition *"When completed the Works shall be fit for the purpose for which the Works are intended as defined in the Contract".* The Contractor has a duty to scrutinise the Employer's Requirements and setting out data at commencement and bring any perceived errors to the attention of the Engineer, who will correct them.

The Engineer's authorities and duties are similar to the Pink Book but with additional duty to review the design submissions and give either consent or approval depending what is specified.

3.2 The Contract

3.2.1 Contract Documents

Construction contracts commonly consist of a number of sections or different documents comprising

Contract Agreement The Contractor's Tender Schedules (including Bill of Quantities or, in lump sum contracts, a Schedule of Rates) General Conditions of Contract Special Conditions of Contract Technical Specifications Drawings Environmental Management Plan

As we have seen, the Conditions of Contract define the entitlements and obligations of the Parties to the Contract. Standard Forms are often used for the General Conditions of Contract. Special Conditions are unique to a particular contract and will contain project specific information such as the contract name and number, the names of the Employer's Representative and Engineer, durations for the Time for Completion and Defects Notification period and other information that is required. The Special Conditions can also be used to modify the General Conditions and add additional requirements. This should always be done with care and it is advisable to have legal opinion for any special conditions that are introduced.

Traditionally the requirements for social safeguards including the protection of the environment were a part of the Technical Specifications. In recent years the need to mitigate risks of damage to the environment during construction work has been given increasing emphasis and the specific requirements are often emphasised by including an Environmental Management Plan as a distinct Contract Document rather than being included in the Technical Specification. This is usually the case with projects funded by the ADB and the World Bank. There are also usually special requirements for social safeguards such as HIV protection and gender equality.

3.2.2 Employer's Technical Specifications (or Employer's Requirements) The Employer's Technical Specifications (or Employer's Requirements in FIDIC) are the parts of the contract documents that define the Permanent Works that form the outcome of the construction work. Although all the documents that form the Contract must be taken as mutually explanatory, the documents that explain the technical requirements are usually considered to be the Specifications, Drawings, EMP and Schedules.

3.2.2.1 PWD Standard Technical Specification for Road and Bridge Works

This document sets out the requirements for materials and workmanship for items of work that are commonplace and generally expected to be a part of every contract. It contains references to items that may be covered in more detail in a Supplementary Specification but contains default requirements which are based on either general conditions applicable in Vanuatu, or minimum requirements for construction. There is an index in the Standard Specification which indicates items where further definition is anticipated in the Supplementary Specification.

3.2.2.2 Supplementary Specification or Project Particular Specification

This document will contain data on things that are specific to the contract such as a description of the Scope of Works, the details of the Site and site specific information and possibly survey control information and setting out data. It will also provide descriptions of the requirements for materials and workmanship for work items that are of a less generalised nature than those in the Standard Specification but are an essential part of the Works to be undertaken. The document will be specially prepared to meet the particular requirements of the design of a particular project and the document will be unique to that project.

3.2.2.3 Drawings

Engineering drawings show the requirements of what is to be constructed. Layout drawings consisting of plans and sections will show the relative position of all the elements of the work to each other and the Site. There may be several sets of layout drawings. For example one set for setting out information, one set for drainage, one for utility services and one for road markings and signs. Layout drawings will be linked to detail drawings which show elements of the works and their dimensions, and often contain information on material requirements.

3.2.2.4 Environmental and Social Management Plan

The EMP will show the perceived adverse impacts that the project may have on the environment and which the Contractor is required to eradicate or mitigate. The contract usually requires the Contractor to respond to the EMP by producing his own project specific Contractor's Environmental Management Plan which provides a set of detailed method statements showing how each risk will be managed and mitigated. As the Standard Specification Group 1 contains a section 1.16 on Environmental Protection care will be needed when preparing the contract documentation to harmonise the various requirements of a separate EMP with the Standard Specification. It may be that the EMP is made a part of the Supplementary Specification or that Sub-clause 1.16 of the Standard Specification is deleted and replaced by the EMP.

The Check Sheets for Group 1 only covers the requirements of the PWD Standard Specification and additional check sheets may need to be prepared to cover the requirements of the Supplementary Specification and/or the EMP. The Supplementary Specification and the EMP may supersede some parts of the Standard Specification.

3.2.2.5 Other requirements

Schedules may contain information on things such as road alignment information; earthworks quantities; the location, levels, size and class of culverts; carriageway

information and junctions; access driveways, fences and road signs; reinforcement bending schedules (if prepared by the Employer).

The Bill of Quantities is usually classed as a Schedule. Sometimes the Pre-amble to a Bill of Quantities will contain important information on the method of measurement for various quantities.

3.2.3 Cross Referencing

The various documents that make up the complete contract set will contain cross references and care should be taken prior to tender to eliminate any anomalies that may exist between the various documents that comprise the Contract.

3.3 The Construction Supervisor

3.3.1 Authority

As we have seen above the authority of the Construction Supervisor (or Engineer in FIDIC) comes from the Conditions of Contract. The authority of any assistants or Representatives of the Construction Supervisor relies on a proper delegation of authority from the Construction Supervisor.

In regard to specific authority for correction of materials and workmanship the following clauses are appropriate:

Vanuatu Works Contract, Clause 5.6.1 *"If the Construction Supervisor is of the opinion that any materials or the work or any part thereof, whether fixed or not, is unsatisfactory he may direct its replacement, removal or correction at the Contractor's expense".*

FIDIC Pink Book and Yellow Book

Clause 7.5 "If, as a result of an examination, inspection, measurement or testing, any Plant, Materials or workmanship is found to be defective or otherwise not in accordance with the Contract, the Engineer may reject the Plant, Materials or workmanship by giving notice to the Contractor, with reasons. The Contractor shall then promptly make good the defect and ensure that the rejected item complies with the Contract".

3.3.2 Delegation

It is highly important that the Construction Supervisor or the Engineer adequately delegates responsibility to his assistants before they proceed to interact with the Contractor.

The delegation should be made in writing from the Construction Supervisor (or Engineer) to the assistant and copies should be issued to both the Contractor and the Employer. The delegation should refer to specific duties in the relevant Conditions of Contract which are to be delegated. Inspectors so delegated must then act within the limits of their delegated authority and not exceed it.

3.3.3 Site Inspection

Contractors are responsible for the safety on the Site. As such they are entitled to make sure that people entering the site or the vicinity of any physical works activities are aware of the risks and that they are correctly attired. It is a requirement for visitors to attend a site safety induction process before being allowed to visit the Site and this should be respected by the Construction Supervisor's staff, notwithstanding their entitlement under the Contract to be given access to the location of any of the Works.

Following the induction process all site visits should be made wearing the correct attire which as a minimum will require safety boots and a reflective jacket, but may also require other attire such as safety helmets and protective goggles.

To carry out comprehensive site checking the inspectors will need certain items of equipment.

Essential items consist of copies of current drawings and the Specification, 5m and 30m tapes, spirit level, camera, notebook and pen. Other equipment needed from time to time depending on the work to be examined will consist of survey equipment, concrete and bitumen thermometers, feeler gauges for crack widths and paint gauges. Any field testing will of course require the requisite testing equipment which must have a current calibration certificate when relevant.

3.3.4 Contractor Notifications and Hold Points

It is usually a requirement that the Contract gives the Construction Supervisor adequate notice of his intention to cover up completed work or to commence certain activities.

This may be a condition of contract as in FIDIC clause 7.7 which states that:-

"The Contractor shall give notice to the Engineer whenever any work is ready and before it is covered up, put out of sight, or packaged for storage or transport. The Engineer shall then either carry out the examination, inspection, measurement or testing without unreasonable delay, or promptly give notice to the Contractor that the Engineer does not require to do so. If the Contractor fails to give the notice, he shall, if and when required by the Engineer, uncover the work and thereafter reinstate and make good, all at the Contractor's cost".

Alternatively, the requirement may come from a statement in the Specification. For example Group 16 Concrete Works which states in clause 16.4 that:- "*The Contractor shall give the Construction Supervisor forty-eight (48) hours' notice of his intention to proceed with the work involved in concreting*".

The Standard Specification does not actually use the term Hold Point which can be defined as a situation where the Contractor cannot proceed with additional work until he has received a formal approval from the Construction Supervisor. There are however many items in the Specification which stipulate that an approval is required and are in effect Hold Points. For example Group 4 clause 4.13 stipulates that:- *"Blasting shall not be undertaken without the Construction Supervisor's approval and only at times approved by the Construction Supervisor".*

The clauses that are considered to be formal hold points have been highlighted in the Check Sheets and formal notification from the Contractor should be submitted.

It is extremely advantageous to good quality management that the requests for inspection should be formalised and a series of sample forms for such notification is included at Appendix A.

3.3.5 Measurement

Measurement Records need to be made jointly on Site with authorised Contractor's personnel as the work progresses. The measurement records will be needed for items of work that will have quantities that cannot be taken off As-built drawings. This covers items

such as removal of unsuitable material from sub-grade level in cuttings or at formation level under embankments.

Level surveys or topographical surveys are also needed after clearing and topsoil removal topsoil and if the nature of the ground in a cutting changes (e.g. from soil to rock)

Notes are provided in the check sheets to identify where measurement records will be needed.

3.3.6 Records

As well as measurement records and check sheet records it is essential that site staff keep adequate records of daily activities on the site, weather, equipment etc. This can be readily done with check sheets that require minimal effort without large amounts of descriptive writing. An example is provided in Appendix B. The value of these records will become apparent as soon as a situation arises in which a Contractor submits a claim for an extension of time and/or additional payment.

4 Quality Assurance System

4.1 Requirements

4.1.1 Contractor's Obligations

The onus should be on the Contractor to establish a comprehensive QA system.

FIDIC clause 4.9 makes it clear. "The Contractor shall institute a quality assurance system to demonstrate compliance with the requirements of the Contract. The system shall be in accordance with the details stated in the Contract. The Engineer shall be entitled to audit any aspect of the system".

The Vanuatu Conditions of Contract do not make mention of a QA system.

The requirement is however covered by the PWD Standard Specification in clause 1.17.2.

It should be a requirement for the Contractor to submit all the results of his QA system as a matter of routine with each interim payment application. It is the Contractor's responsibility to demonstrate to the satisfaction of the Contract Supervisor that all the materials brought to Site for incorporation into the Works are in compliance with the requirements of the Specifications. The Contractor should not be relying on the checks and tests being carried out by the Supervisor which are carried out for the purposes of independent verification of the Contractor's results. Approval of work for payment should be withheld in cases where compliance with contract requirements is in doubt until the Contractor has fulfilled the obligation to demonstrate compliance.

4.1.2 Quality System Audit

The first opportunity to audit the Contractor's quality assurance system comes with approval of the Quality Plan. This should be done with all due diligence.

Once the QA Plan is approved then there can be formal audits from time to time to check that the approved system is being carefully adhered to. This should be carried out whenever the Contractor submits a request for an interim payment because it should be a requirement to demonstrate compliance with the Specification for all work included in a payment request.

Payment should not be made for items of work which have not been verified by the Contractor's QA system.

Thirdly there is a need for routine and specific verification testing by the Contract Supervisor.

This is done as a matter of routine through the process of the site inspections using the check sheets. If the Construction Supervisor has a full time representative on the Site then it is being carried out on a daily basis. Alternatively there may be only periodic inspections.

A specific decision may be made to carry out an audit if suspicion is aroused that some work may not have been adequately executed. In this case the Construction Supervisor has the power to have already completed work opened up for inspection and testing.

The Vanuatu Works Contract states at clause 5.6.5 that:- The Construction Supervisor may instruct the Contractor to search for a Defect and to uncover and test any work that the Construction Supervisor considers may have a Defect.

In FIDIC clause 7.7, as already mentioned, gives an automatic right to have any work covered up without adequate prior notice. Also clause 11.8 states:- "The Contractor shall, if required by the Engineer, search for the cause of any defect, under the direction of the Engineer".

These powers should be used wisely because if work is opened up and defects are not found then the cost of opening, additional testing and reinstatement will fall upon the Employer.

4.1.3 Testing Requirements

The type of testing and the amount of testing is stipulated in the Specification. In some Groups the Standard Specification implies that the details such as lot sizes and the number of tests per lot will be included in a Supplementary Specification. Otherwise the Construction Supervisor is empowered to instruct on these matters. It is important to clarify these matters at the start of the contract. Instructions for additional testing at a later stage in the contract are likely to lead to claims for a Variation.

It is the Contractor's obligation to carry out the testing and provided copies of results to the Construction Supervisor. It is important to check at the outset that the Contractor has competent people to carry out this work and to check that all the equipment that will be used has current calibration certificates.

The Construction Supervisor is entitled to carry out his own testing for the purposes of random verification.

Supervisors also have powers to instruct the Contractor to carry out additional testing but when results are positive the Employer may have to pay the costs of the testing and the costs of any delay that was caused. Clause 7.4 FIDIC states:-

"The Engineer may, under Clause 13 [Variations and Adjustments], vary the location or details of specified tests, or instruct the Contractor to carry out additional tests. If these varied or additional tests show that the tested Plant, Materials or workmanship is not in accordance with the Contract, the cost of carrying out this Variation shall be borne by the Contractor, notwithstanding other provisions of the Contract".

Clause 5.6.5 (2) in the Vanuatu Works Contract sates:-.

"If the Construction Supervisor instructs the Contractor to carry out a test not specified in the Specification to check whether any work has a Defect and the test shows that it does, the Contractor shall pay for the test and any samples. If there is no Defect, the cost of testing will be compensated by the Employer to the Contractor".

4.2 Check Sheets

4.2.1 General

The Check Sheets are sequenced in Groups according to the layout of the PWD Standard Specification for Road and Bridge Works. The same paragraph reference numbers that are used in the Specification are also used as references in the Check Sheets.

The check sheets are in the form of a series of questions that require a 'Yes' or 'No' answer. If any of questions in the Check Sheets are answered with a 'No' it means that there is a default by the Contractor who is not meeting some requirement of the Specification. Whenever the answer to a question in the check sheet is 'No' there will need to be an instruction issued by the Construction Supervisor or a delegate informing what action has to be taken by the Contractor to rectify the default. If the default cannot be rectified by the Contractor during the course of the site visit where it has been identified the instruction will need to be issued in writing and the item of work it will require re-checking during a future visit.

4.3 Using the Check Sheets

It is intended that those people carrying out a site inspection or quality audit on behalf of the Construction Supervisor will print out the relevant forms and complete them as part of the inspection or audit.

Each Sheet contains 4 sub-sections covering issues that need to be addressed before any physical work commences; issues that need to be checked during construction work or following completion; testing that needs to be carried out at the Site or in the laboratory; and site measurement records that may be required

Inspectors and Supervisors should systematically work through each sheet that covers the ongoing works which will then provide a complete record of how the Contractor is responding to all the requirements of the Specification.

The signed off check sheets and measurement records, which in general will represent measurements jointly agreed between the Supervisor and the Contractor, may be used to justify interim and final payments to the Contractor.

Wherever the answer to one of the questions in the check sheet is 'no' the default response shall be **"Supervisor shall issue appropriate instructions".** The answer 'no' indicates a non-compliance with the contract requirements and corrective action is required by the Contractor.

A responsible Contractor will correct any non-compliance as a matter of course. However, in line with the usual contract requirements to confirm instructions in writing, a written instruction should follow up any verbal instruction. If the corrective action is carried out in the

presence of the Supervisor so that the 'no' in the check sheet can be changed to a 'yes' during the time of the site visit then a follow up written instruction can be waived.

If the person carrying out the inspection is not suitably authorised to issue an instruction that may be required then that person's task is to ensure that a suitably authorised person does issue the instruction, in writing.

Remember, whenever the answer to a question in the check sheet is 'No' there will need to be an instruction issued to the Contractor by the Construction Supervisor or a delegate.

A sample form for providing an instruction to the Contractor is included at Appendix C.

4.4 List of Check Sheets

GROUP 1 GENERAL CLAUSES

GROUP 2 ESTABLISHMENT

GROUP 3 CLEARING AND GRUBBING

GROUP 4 EARTHWORKS

GROUP 5 BASE AND SUB-BASE PAVEMENT COURSES

GROUP 6 HAND PACKED STONE (PAVEMENTS)

GROUP 7 REONFORCED CONCRETE PAVEMENTS

GROUP 8 BITUMINOUS SURFACING

GROUP 9 DRAINAGE

GROUP 10 ROAD FURNITURE AND MARKINGS

GROUP 11 MASONARY FOR STRUCTURES

GROUP 12 PILING FOR STRUCTURES

GROUP 13 FALSEWORK

GROUP 14 FORMWORK FOR CONCRETE

GROUP 15 STEEL REINFORCEMENT

GROUP 16 CONCRETE FOR STRUCTURES

GROUP 17 STRUCTURAL STEELWORK

GROUP 18 PROTECTION OF STEELWORK

GROUP 19 MISCELLANEOUS BRIDGEWORK ITEMS

GROUP 20 RIVER TRAINING AND BANK PROTECTION

GROUP 21 DAYWORKS

GROUP 1 – GENERAL CLAUSES					
CHECK	SHEET 1A - C	Checks Required before physical works con	nmence	Э	
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")	
1.8	Traffic Manage- ment				
1.8.1	General	Have details of proposed temporary traffic diversions been submitted and approved?			
		Have full details including calculations been submitted for any temporary bridges that are required?			
		for road closures for prior approval?			
1.8.2	Traffic Manage- ment Plan	Has the Contractor submitted a Traffic management Plan covering the items listed in this clause of the Specification, at least 21 days prior to commencement?			
1.9	Setting Out	Have sufficient control points been established and their location details advised to the Contractor within 14 days of a request from the Contractor?			
1.10	Construct- ion Procedures	Has the Contractor submitted detailed erection proposals for all bridges at least 7 days prior to commencing erection of any members of a bridge structure?			
		Has the Contractor included calculations to demonstrate that the temporary works will be stable and not overstressed, and that the Permanent Works will not be damaged in any way by the erection procedures?			
1.14	HIV/AIDS Prevention	Has the Contractor submitted a HIV/AIDS Awareness and Information Programme for the Site and all other sites related to the Works, at least 21 days prior to Commencement?			
		Has the Contractor nominated a qualified service provider for the implementation of the HIV/AIDS Awareness and Information Programme?			
1.15.2	Contractor's Safety Programme	Has the Contractor submitted a Safety Programme for the Site and all other sites related to the Works, at least 21 days prior to Commencement?			
		Is the Safety Programme in compliance with the Vanuatu Health and Safety at Work Act and any appropriate Public Works Department Work Safety Guidelines and does it cover all the items (a) through (h) listed in this clause of the Specification?			

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
1.16.2	CEMP	Has the Contractor submitted, within 28 days of signing the Contract and before commencing any work on Site, the Contractor's Environmental Management Plan (CEMP) for the Site and all other sites related to the Works?		
		Does the CEMP cover all the requirements (a) through (m) of this clause of the Specification?		
1.17.2	Contractors Quality Control Plan	Has the Contractor submitted a Quality Control Plan (QCP) for the Works at least twenty one (21) days prior to commencement?		
		Does the QCP cover all the items (a) through (g) of this clause of the Specification?		
1.18	Community Liaison			
1.18.1	General	Has the Contractor visited all affected communities before commencing work on Site [in company with the Provincial Planner, a representative of the Provincial Council of Chiefs and the relevant Community Chief(s)] to explain construction activities?		
1.18.2	Community Liaison Plan	Has the Contractor submitted a Community Liaison Plan (CLP) for the Works at least twenty one (21) days prior to commencement?		
		Does the CLP cover the items described in the 6 bullet points of this clause in the Specification?		
1.18.3	Community Liaison Officer	Has the Contractor appointed a Community Liaison Officer?		
1.18.6	Local labour	Has the Contractor specifically nominated any foreign personnel and sub-contractors and does their residential status comply with the immigration regulations and the Labour Act?		
Notes				

Name

SignatureDate

GROUP 1 – GENERAL CLAUSES						
CHECK	SHEET 1B - CI	hecks Require During or After Physical W	orks			
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")		
1.8	Traffic					
	Management					
1.8.1	General	Have sufficient and clearly delineated temporary signs, barriers and marker posts been erected to guide traffic through the working areas?				
		Have all existing signs that are required to				
		be removed temporarily or permanently being carefully stored?				
		Have all existing signs that were removed only temporarily been reinstated in a satisfactory manner?				
		Have all existing signs that are not				
		required for re-use on the contract been delivered to the nearest PWD depot?				
1.11	Loading Limits on Public Roads	Is the Contractor observing the loading limits of the Road Traffic Control Act?				
1.14.2	HIV/AIDS Awareness programme	Is the Contractor implementing the awareness programme using an approved service provider and in compliance with all the requirements of this clause of the Specification?				
1.15.2	Contractor's Safety Programme	Is the Contractor implementing the approved Safety Programme and carrying out all the requirements of the second sub series (a) though (j) of this clause of the Specification?				
1.16.2	CEMP	Is the Contractor reviewing the CEMP monthly and updating as necessary?				
		Is the Contractor incorporating compliance with the CEMP into the conditions of any Sub-Contractor agreements?				
		Have all Contractor personnel undergone induction training into the application of the CEMP?				
		Is the Contractor maintaining a register of inducted personnel?				
		Is the Contractor recording non- conformances with the CEMP and providing a monthly summary?				

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
		Is the Contractor reporting any environmental incidents to the Construction Supervisor?		
1.17.2	Contractors Quality Control Plan	Is the Contractor implementing the QCP on a routine basis during the execution of the Works?		
1.18	Community Liaison			
1.18.3	Community Liaison Officer	Is the Community Liaison Officer actively pursuing the tasks listed in this clause of the Specification?		
1.18.4	Induction	Has the Contractor carried out induction training of all personnel to cover standards of social behaviour, cultural practice and gender awareness?		
1.18.5	Gender Awareness	Is the CLO implementing a Gender Awareness Programme to promote opportunities for women as participants and beneficiaries of development programmes?		
		Has the Contractor submitted reports on the implementation of the gender awareness programme at bi-monthly intervals and prior to the issue of the Taking over Certificate?		
1.18.6	Stakeholder Committees	Has the CLO established the Stakeholder Committees in conformance with this clause of the Specification?		
1.18.7	Local Labour	Is the Contractor making reasonable attempts to engage local community groups and women's groups for aspects of the work?		
1.18.8	Grievance Resolution	Has the CLO established a suitable Grievance Redress Procedure and a Register of Complaints?		

Notes	
Name	
Signature	
Date	

GROUF	GROUP 1 – GENERAL CLAUSES						
CHECK	SHEET 1C – Labo	ratory or Field Tests Required					
clause	Title	Check	Satisfactory Test results provided?				
	Not Relevant						

	GROUP 1 – GE	NERAL CLAUSES		
	CHECK SHEET	1D – Measurement Records		1
Clause		Check	Unit	Y/N
	Measurement			
	and Payment			
100		All inclusive Lymp Cym byt to be apportioned	0/ of	
1.0.3	(Trainc	for normant on a monthly basis	% 0I	
	management)	for payment on a monthly basis.	LO	
		Has the Contractor been issued with any notices		
		of non-compliance with the TMP which have not		
		been rectified?		
		Note: An unspecified amount can be deducted		
		from the monthly portion of the payment for		
		notified matters that have not been corrected in		
		the specified time		
1.14.3	(HIV/Aids	Lump Sum. 30% upon acceptance of the	% of	
	awareness)	Awareness Programme and the balance of 70%	LS	
		apportioned over the contract duration.		
		A separate lump sum amount may be included		
		In the BoQ for stocking condom dispensers and		
		maintaining awareness posters.		
		Has the Contractor submitted the monthly		
		Compliance Report Form?		
		Has the Contractor been issued with any notices		
		of non-compliance with the approved		
		Programme which have not been rectified?		
		Note: An unspecified amount can be deducted		
		from the monthly portion of the payment if a		
		notified matter has not been corrected in the		
		specified time.		
1 15 3	(Safety	All-inclusive Lump Sum but to be apportioned	% of	
1.10.0	Programme)	for payment on a monthly basis	IS	
	l'rogrammo,		20	
		Has the Contractor been issued with any notices		
		of non-compliance with the approved Safety		
		Programme which have not been rectified?		
		Note: An unspecified amount can be deducted		
		from the monthly portion of the payment for		
		notified matters that have not been corrected in		
1 16 2	(Environmentel	the specified time	0/ of	
1.10.3	(Environmental	for payment on a monthly basis	% 0I	
			13	
		Has the Contractor been issued with any notices		
		of non-compliance with the Approved CEMP		
		which have not been rectified?		
		Note: An unspecified amount can be deducted		
		from the monthly portion of the payment for		
		notified matters that have not been corrected in		
		the specified time		

Clause	Title	Check	Unit	Y/N
1.17.3	(Quality	All-inclusive Lump Sum but to be apportioned	% of	
	Control Plan)	for payment on a monthly basis.	LS	
		Has the Contractor been issued with any notices of non-compliance with the Approved QCP which have not been rectified? Note: An unspecified amount can be deducted from the monthly portion of the payment for notified matters that have not been corrected in the specified time		
1.18.9	(Community	All-inclusive Lump Sum but to be apportioned	% of	
	Liaison)	for payment on a monthly basis.	LS	
		Has the Contractor submitted the monthly summary of community liaison activities? Has the Contractor been issued with any notices of non-compliance with the required community liaison activities which have not been rectified? Note: An unspecified amount can be deducted from the monthly portion of the payment for notified matters that have not been corrected in the specified time		

Notes	
Name	
Signature	
Date	

Form 2A Page 1 of 1

Project Na	me	 	
Chainages	From	 То.	

GROUP 2 – ESTABLISHMENT						
CHECK	SHEET 2A - C	Checks Required before physical works co	mmen	ice		
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")		
		NOT RELEVANT				

GROUP	2 – ESTABLIS	HMENT				
CHECK	CHECK SHEET 2B - Checks Require During or After Physical Works					
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")		
2.1.1	General	Do all accommodation units, offices,				
		sheds and storage units meet the				
		requirements of the relevant Health and Safety Regulations?				
		Are suitable arrangements in place for				
		the collection and disposal of wastes?				
2.2.2	Construction	Is the office erected in compliance with				
	Supervisor's	the specified requirements and in the				
	Office	correct location within one month of				
		contract award by letter of acceptance?				
		Has all the specified furniture and				
		equipment been delivered?				
2.3	Notice	Have the required notice boards been				
	Boards	erected on the site in conformance with				
		the details on the drawings?				
		After completion, have the notice boards				
		been removed and the sites where they				
		were located left in a neat and tidy				
		condition?				

Notes	
Name	
Signature	
Date	

GROUF	GROUP 2 – ESTABLISHMENT					
CHECK	SHEET 2C – Labo	ratory or Field Tests Required				
clause	Title	Check	Satisfactory Test results provided?			
		NOT RELEVANT				

Form 2D Page 1 of 1

Project Na	me	 		 	 	
Chainages	From	 ••••••	То	 	 	•••

	GROUP 2 – ESTABLISHMENT								
	CHECK SHEET	CHECK SHEET 2D – Measurement Records							
Clause	Title	Check	Unit	Y/N					
2.1.2	Establishment Item in Bill	Is the Contractor established on the site in conformance with all the issues listed in this clause of the Specification to the satisfaction of the Construction Supervisor?	LS						
2.1.4	Demobilisation	Has demobilisation covering all items listed in this clause been completed to the satisfaction of the Construction Supervisor?	LS						

GROUP	GROUP 3 - CLEARING AND GRUBBING				
CHECK	SHEET 3A -	Checks Required before physical works co	mmer	ice	
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")	
3.1	Clearing and Grubbing	Is the 'Area' to be cleared covered by items (i) to (iv) of this sub-clause and/or clearly marked on the drawings? <i>Note: It is suggested that the extent of the</i> <i>clearing limits be staked out</i>		Issue instructions to designate the 'Area'	
		Have any trees which are to be preserved been clearly indicated?		Mark trees to be preserved	
		Have any necessary instructions for Grubbing been issued? Note: the term 'objectionable material' is not defined. Suggest this is confined to material above ground level eg piles of trash, car wrecks. Objectionable material below ground level will be addressed in GROUP 4 EARTHWORKS		Issue any necessary instructions	
		Have items that are to be removed but which are not covered by the Pay Item for Clearing and Grubbing been measured? <i>Note: this covers concrete headwalls,</i> <i>culverts, foundations</i>		Carry out joint measure	
3.1.1	Clearing	Has the Contractor taken the necessary precautions to prevent damage to structures and other private or public property?		Issue instruction	
3.1.2	Grubbing and Stripping of Topsoil	Has suitable 'selected material' been proposed and approved for the backfilling of holes from which obstructions are removed?		Instruct Contractor to submit proposal	
		Have any necessary instructions for the stockpiling and/or transport of topsoil been issued? Note: If drawings or the Supplementary Specification do not show where topsoil is to be a stockpiled an instruction may be required.		Issue instructions as necessary	
3.2	Clearing of Stream Crossing Sites	Have necessary instructions for limits of work and felling of nearby trees been issued?		Issue instructions as necessary	
3.3	Clearing of Existing Drainage Paths	Are any/all slips or slumps less than 5m ³ ?		Arrange joint measure of slips greater than 5m ³	

Clause	Title	Check	Y/N	Response if N Default is " issue instruction")
3.4	Disposal of Material	Is disposal by burning in the central parts of the 'Area' acceptable?		If not instruct alternative method.
		For disposal areas outside the Site has the Contractor shown that he has made suitable arrangements with property owners?		Instruct Contractor to show evidence of suitable arrangements
3.6	Removal of Existing Bridge Structures	Is the super-structure to be dismantled so that materials can be re-used?		Issue instruction that demolished materials are to be classified as waste
		Is removal of foundations stipulated in the drawings or Supplementary Specification, and IF NOT can bridge foundations be left in place?		Issue instructions for removal under Group 4

Notes	
Name	
Signature	
Date	

GROUP 3 - CLEARING AND GRUBBING				
CHECK	SHEET 3B - C	hecks Require During or After Physical V	Vorks	
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
3.1	Clearing and Grubbing			
		Has the work been completed to the extent required?		
		Have branches of trees that are to be left standing been pruned to 7m above road level?		
3.1.1	Clearing of Vegetation	Have fences that have been cut been made good or continued in a different direction?		
3.1.2	Grubbing	Have any holes from which stumps or obstructions have been removed been adequately backfilled with approved selected material and thoroughly compacted?		
		Has the ground surface been graded to an even finish?		
3.2	Clearing Stream Crossings	Has the work been completed satisfactorily?		
3.3	Clearing of Drainage Paths	Has the work been completed satisfactorily?		
3.4	Disposal of Material	Has all cleared and grubbed material been satisfactorily disposed of?		
3.5	Removal of Existing Bridge Structures	Has all work been carried out satisfactorily according to Specification and Instructions?		
		Have piles been cut off 1m below river bed?		

Notes	
Name	
Signature	
Date	

GROUP 3 - CLEARING AND GRUBBING				
CHECK	CHECK SHEET 3C – Laboratory or Field Tests Required			
clause	Title	Check	Satisfactory Test results provided?	
3.1	Clearing and Grubbing	No testing is specifically required but the Contractor has to use a 'selected material' to backfill any stump holes which must be 'well compacted'. The definition for 'selected material' is not provided and may require instruction and testing.		

Notes	
Name	
Signature	
Date	

	GROUP 3 - CLEARING AND GRUBBING CHECK SHEET 3D – Measurement Records			
Clause	Title	Check	Unit	Y/N
3.1	Clearing and			
	Grubbing			
		Measurement records should be jointly agreed	m ³	
		for Concrete Headwalls, Wing walls, Box		
		culverts, Foundations which are to be removed		
		and paid under Pay Item 4.5.4		
		Measurement Records should be made for pipe	L	
		culverts which are to be removed and stacked or		
		transported according to item 7.6 (Group 7)		
3.1.2		Measurement records should be jointly agreed	m ³	
		for stump holes that are to be backfilled with		
		selected material and paid under item 4.23		
3.3	Clearing	Measurement Records should be jointly agreed	m ³	
	drainage	for any slips and slumps greater than 5m ³ .		
	paths	Slips and Slumps less than 5m ³ are deemed to		
		be included in the linear metre rate for clearing		
		drainage paths		
3.5	Measurement	Clearing and Grubbing	hectare	
	and Payment	Note: Clearing, Grubbing and Topsoli removal to		
		<u>a depth of 150mm</u> mm is paid under a single		
		Item. This item also covers stockpilling and/or		
			No	
		Stream Crossings	INO.	
		Existing Drainage Paths	m	
3.6	Pomoval of	Should normally be a lump sum but may need		
3.0	Evicting	soparate measurement of foundations if		
	Bridge	instructions have been issued for removal of		
	Structures	foundations under GROUP 4		

Notes	
Name	
Signature	
Date	

GROUP 4 - EARTHWORKS				
CHECK SHEET 4A - Checks Required before physical works commence				
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
4.20.1 and 4.22.1	Measure- ment and Payment for General Excavation and Embank- ment	Has a topographical level survey been carried out after the completion of clearing and grubbing works under GROUP 3? <i>Note: Sub-clause states "The cross</i> <i>sectional area to be used shall be that</i> <i>area bounded by the required finished sub</i> <i>grade, the required side slopes and the</i> <i>original ground level as it exists <u>after</u> <u>clearing, grubbing and topsoil stripping</u> <u>operations have been completed"</u>.</i>		
4.2.1	Dimensions	Have any necessary instructions been issued regarding changes to dimensions, slopes or levels shown on drawings?		
4.13	Use of Explosives	Has the Contractor given at least ten (10) days' notice of any intention to excavate by blasting and supplied full details of the location and the methods he proposes to adopt?		This is a Hold Point
		Has the blast management plan been submitted and approved Note: AS 2187.2 requires a blast management plan to be prepared and that no blasting is to be carried until the plan has been approved by a competent person. The plan must include, but is not limited to, risk management; a site safety plan; and blast design.		This is a Hold Point
4.14.4 and 4.15.4	Notice	Has the Contractor submitted samples of the material proposed for use in the upper layer of embankment fill, at least 7 days prior to commencement of the work?		This is a Hold Point
4.18	Borrow	Has the Contractor demonstrated that he has planned the earthworks operations to maximise the use of suitable materials obtained from excavations and to minimise the requirements for the use of Borrow? <i>Note: This may require a detailed method</i> <i>statement including assessment of</i> <i>different types of materials and including a</i> <i>Mass/Haul diagram</i>		Do not approve the use of Borrow until evidence of earthworks planning is produced
4.19.1	Fill to Structural Foundation - General	Has the Contractor submitted the proposed construction procedure for approval prior to commencement of the work?		This is a Hold Point
4.19.5. 1	Fill to Bridge abutments- General	Has the Contractor submitted the proposed method for the backfill of bridge abutments for prior approval?		This is a Hold Point
Form 4A Page 2 of 2 Project Name..... Chainages From......To.....

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
4.19.5. 1	Fill to Bridge abutments- General	Has the Construction Supervisor carried out and inspection and satisfied himself concerning pertinent foundation conditions that may affect the future stability of the bridge or embankment?		This is a Hold Point
4.25.1	Construction Compliance Testing	Has the Construction Supervisor directed the number and frequency of testing that is required?		

Notes	
Name	
Name	
Signature	
Date	

GROUP 4 - EARTHWORKS (Cut)					
CHECK SHEET 4BCut - Checks Require During or After Physical Works					
		(note that the sequence followed with			
		clause references is to suit the work stages)			
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")	
4.5	General Excavation				
4.5.1	General	Did Contractor provide notice when the material type in a cutting changed, so that measurements could be taken? Note: Ripping trials may be needed to classify materials and should be witnessed. A Bulldozer of 370 HP is specified for ripping trials which is equivalent to a Caterpillar D8/D9 and is unlikely to be available in most instances. Some alternative method of classification may be required.		Construction Supervisor may determine respective quantities unilaterally if notice was not given	
4.2.1	Dimensions	Are the dimensions of the excavations in accordance with the cross sections and longitudinal profile shown on the Drawings and such additional details as provided by the Schedule of Works?			
4.2.3	Side Slopes	Have side slopes been trimmed neatly and evenly to the lines and slope shown on the Drawings?			
4.2.4	Existing Pavement	Have joints between new and existing pavement been stepped 150mm vertical and 300mm horizontal when the existing pavement is greater than 200mm thick?			
4.6.1	Unsuitable material in Excavation	Has all unsuitable material (and surplus material) from excavation been disposed of to approved locations in a manner that is stable well drained and of neat appearance?			
4.5.6	Compaction of Insitu Sub- grade	Has the in-situ subgrade been compacted to 98% MDD as established by AS 1289.5.1.1 (Standard Compaction)?			
4.6.2	Unsuitable material in Subgrade	Has unsuitable material been identified at sub-grade level in cuttings? Note: It is common practice to extensively check the sub-grade using a DCP or similar equipment to identify if and where the design CBR requirement is not met.		Instruct areas and depths of additional excavation	
4.3	Tolerance	Has sub-grade level been checked and conformed as being not higher and not more than 50mm lower than the required level?			

Project Na	me
Chainages	FromTo

Title	Check	Y/N	Response if N (default is "issue instruction")
Rock Cuts	Has a bern of at least 600mm been left between the top of slope of rock cuttings and the toe of slope of overlying materials?		
	Has the rock been excavated to at least sub-grade level and trimmed to a reasonably smooth and uniform level?		
	Have any pinnacles of rock and broken rock less than 150mm diameter been removed?		
	Have rock cuts been brought up to subgrade level by backfilling with approved material?		
	Is excavated rock that is of suitable quality being reserved for use as stone pitching, gabion fill etc.?		
Dangerous and Overhanging Rock	Is there any dangerous, loose and overhanging rock within or outside the limits of the road right-of-way?		
Excavation for Structural Foundations – Execution of the Work	Has the material at the base of the excavation been inspected and approved as suitable? Note: it would be advantageous if this was a Hold Point. If additional excavation is required see 4.19.3 for details of backfill		Instruct additional depth of excavation. If the material is unsuitable due to Contractor neglect. Additional excavation and backfill will not be measured for payment in this situation.
Use of Explosives	Has the blast management plan required by AS 2187.2 been approved?		This is a Hold Pont
	Are the handling, storing and use of explosions being carried out in compliance with the requirements of AS 2187.1 and AS 2187.2? <i>Note: The AS 2187 series are substantial</i> <i>documents with very many issues that</i> <i>require careful attention</i> If blasting is taking place near buildings, is the Contractor operating a vibrograph or similar instrument to monitor vibrations? Are the persons handling explosives trained and experienced?		
	Title Rock Cuts Rock Cuts Dangerous and Overhanging Rock Excavation for Structural Foundations – Execution of the Work Use of Explosives Use of Explosives	Title Check Rock Cuts Has a bern of at least 600mm been left between the top of slope of rock cuttings and the toe of slope of overlying materials? Has the rock been excavated to at least sub-grade level and trimmed to a reasonably smooth and uniform level? Have any pinnacles of rock and broken rock less than 150mm diameter been removed? Have rock cuts been brought up to subgrade level by backfilling with approved material? Is excavated rock that is of suitable quality being reserved for use as stone pitching, gabion fill etc.? Dangerous and Overhanging Rock Excavation for Structural Foundations - Execution of the Work Has the material at the base of the excavation been inspected and approved as suitable? Note: it would be advantageous if this was a Hold Point. If additional excavation is required see 4.19.3 for details of backfill Use of Explosives Has the blast management plan required by AS 2187.2 been approved? Are the handling, storing and use of explosions being carried out in compliance with the requirements of AS 2187.1 and AS 2187.2? Note: The AS 2187 series are substantial documents with very many issues that require careful attention If blasting is taking place near buildings, is the Contractor operating a vibrograph or similar instrument to monitor vibrations? Are the persons handling explosives trained and experienced?	Title Check Y/N Rock Cuts Has a bern of at least 600mm been left between the top of slope of rock cuttings and the toe of slope of overlying materials? Has the top of slope of overlying materials? Has the rock been excavated to at least sub-grade level and trimmed to a reasonably smooth and uniform level? Have any pinnacles of rock and broken rock less than 150mm diameter been removed? Have rock cuts been brought up to subgrade level by backfilling with approved material? Is excavated rock that is of suitable quality being reserved for use as stone pitching, gabion fill etc.? Dangerous and Overhanging Rock Is there any dangerous, loose and overhanging rock within or outside the limits of the road right-of-way? Note: it would be advantageous if this was a Hold Point. Has the material at the base of the excavation been inspected and approved as suitable? Note: it would be advantageous if this was a Hold Point. Has the blast management plan required by AS 2187.2 been approved? Are the handling, storing and use of explosives As 2187.2 been approved? Are the handling, storing and use of explosions being carried out in compliance with the requirements of AS 2187.1 and AS 2187.2? Note: The AS 2187 series are substantial documents with very many issues that require careful attention If blasting is taking place near buildings, is the Contractor operating a vibrograph or similar instrument to monitor vibrations? Are the persons handling explosives trained and experienced?

Project Na	ne	
Chainages	FromTo	

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
4.13	Use of Explosives (continued)	Has the Contractor provided sufficient screens, barriers, mats to limit the effects of blasting?		
		Are storage locations and work areas appropriately marked with warning signs?		
		Is a means of providing an audible signal prior to blasting in place?		
		Are lookouts in place to prevent access by unauthorised people?		

Notes	
Neme	
Name	
Signature	
-	
Date	
Date	

GROUP 4 - EARTHWORKS (Fill)							
CHECK	CHECK SHEET 4BFill - Checks Require During or After Physical Works						
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")			
4.14	Rock Embankment						
4.14.1	General	Are rock embankments being constructed in layers equal in thickness to the largest average size of the material but not exceeding 600 mm? Are materials being deposited and spread so that the large rocks are well distributed and the intervening spaces filled with smaller sizes? Note: Supervisor has some discretion to allow larger lifts if material can be spread satisfactorily.					
4.14.2	Compaction	Has compaction to demonstrate negligible movement under the roller been witnessed? Note: Compaction is to be carried out by a vibrating roller or grid roller with a static load per 100 mm width of roll of at least 1.75 kN or 7.8 kN respectively					
4.14.3	Upper layer	Is the upper layer of the embankment (i.e. the sub-grade) being constructed with approved material in layers of maximum thickness 200mm? Note Material to be maximum size 75mm and to have a minimum 4 day soaked CBR of 15% obtained from test AS 1289.6.1.1. Contractor to provide a sample at least 7 days prior to placement Has the field compaction been					
		from test AS 1289.5.1.1?					
4.15	Earth Embankment						
4.15.1	General	Has the in-situ soil under embankments (after stripping of topsoil) been compacted to a characteristic value of 95% of the MDD determined by AS 1289.5.1.1 for a depth of 150 mm? Note: if it is shown to be impractical to achieve this level of compaction then the Construction Supervisor may instruct a bridging layer of granular material with strong mechanical interlock and low sensitivity to moisture.					

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
4.15.2		Have the slopes of the original ground or embankment (except rock embankments) been terraced or stepped before filling is commenced?		
4.15.1	General	Are earth embankments being constructed in successive horizontal layers not exceeding 300 mm in loose thickness, (or layers not exceeding 200mm in loose thickness for the top 600mm)		
4.15.2	Compaction	Is each layer being compacted to a Characteristic Value of 95% of the MDD as determined by AS 1289.5.1.1? <i>Note: Contractor is deemed to have allowed</i> <i>in rates for drying out if that is required</i>) <i>See Specification for use of soil that cannot</i> <i>be dried back to obtain this level of</i> <i>compaction and issue instructions as</i> <i>necessary.</i>		
4.15.3	Upper Layer	Is the upper layer of the embankment (i.e. the sub-grade with thickness at least 3000mm) being constructed with approved material in layers of maximum thickness 200mm? Note Material to be maximum size 75mm and to have a minimum 4 day soaked CBR of 15% obtained from test AS 1289.6.1.1. Contractor to provide a sample at least 7 days prior to placement		
		Has the field compaction of the upper layer been demonstrated to be 98% MDD obtained from test AS 1289.5.1.1?		
4.15.5	Trimming	Have embankment slopes been trimmed to provide a neat finish to the lines shown on the Drawings?		
		Has sub-grade level been trimmed to provide a neat finish of sub-grade surface to the lines shown on the Drawings with a tolerance of plus zero and minus 50mm?		
		Has the clearing of any waterways of debris arising from the embankment operation and trimming been carried out?		
4.15.6	Placement of Topsoil	Has topsoil been placed, trimmed and lightly compacted on the embankment slopes? Note: Unless otherwise specified minimum depth shall be 75mm.		
4.18	Borrow	Has the use of Borrow been approved prior to importing material to the Works?		No payment for unapproved Borrow

Project Na	me	 	
Chainages	From	 То	

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
		Are Borrow pits being excavated so that they will drain?		,
		Have Borrow Pits been staked out and cross-sectioned prior to commencement of excavation?		No excavation allowed until pit staked out
		Have side slopes of Borrow Pits been trimmed and dressed to suitable slopes?		
4.19	Fill for Structural Foundations			
4.19.1	General	Has the proposed construction method been submitted and approved?		Do not allow work to commence
4.19.2	Placing fill	Has fill of sub-base standard been placed in maximum 200mm layers and compacted to 95%MDD determined from AS 1289.5.1.1 (Standard Compaction)		
4.19.3	Backfill below foundation	Does the backfill to any over excavation of a structural foundation consist of lean mix concrete or sub-base quality material?		Reject other materials
		If Sub-base material has it been placed in maximum 200mm layers and compacted to 95% MDD determined from AS 1289.5.1.1 (Standard Compaction)		
4.19.4	Backfill to Excavation	Has the backfill of the excavation after installation of the foundation been carried out using an approved material?		
		Has the backfill been placed in even layers not exceeding 300 mm thick and compacted to at least 95% MDD in accordance with AS 1289.5.1.1. (standard compaction)		
4.19.5	Fill to bridge abutments	Has the Contractor received approval for the proposed method of carrying out the work?		No work to commence until consent given to method
		Does backfill material conform to sub-base requirements? Note: Compaction requirement for backfill is not stipulated but needs to be carried out to a high standard as settlement behind abutments is a common problem. 100% MDD from Modified Compaction would be a good standard		
1			1	1

Project Na	me		
Chainages	From	То	

Clause	Title	Check	Y/N	Response if
				Ν
				(default is
				"issue
				instruction")
4.19.5	Fill to bridge	Has a drainage layer been constructed		
	abutments	according to the drawings or otherwise as		
	(continued)	described in the Specification?		

Notes	
Name	
Signature	
Oignature	
Date	

GROUP 4 - EARTHWORKS					
CHECK	CHECK SHEET 4C – Laboratory or Field Tests Required				
clause	Title	Check	Y/N	Satisfactory Test results provided?	
4.5.6	Compaction of In-situ Subgrade in Excavation	Subgrade to be compacted to 98% MDD obtained under AS 1289.5.1.1 (Standard Compaction)			
4.6.2	Unsuitable Material in Sub-grade	Testing is required to demonstrate that sub- grade has the minimum design CBR value, commonly using a DCP. Contractor testing should be witnessed or testing should be carried out independently			
		If unsuitable material is replaced with approved selected material then retesting for compaction will be required.			
4.14.3	Rock Embankment – Upper Layer	Material for upper layer (at least the top 300mm) to be maximum size 75mm and demonstrate 4 day soaked CBR of 15% (Test AS 1289.6.1.1)			
		Field compaction to be 98% MDD obtained from test AS 1289.5.1.1 (Standard Compaction)			
4.15.1	Earth Embankment s-General	Insitu soil underlying embankments to be compacted to 95% MDD obtained from AS 1289.5.1.1 (Standard Compaction)			
4.15.2	Compaction	Each layer of embankment soil to be compacted to 95% MDD obtained from AS 1289.5.1.1 (Standard Compaction)			
4.15.3	Upper layer	Material for upper layer (at least the top 300mm) to be maximum size 75mm and demonstrate 4 day soaked CBR of 15% (Test AS 1289.6.1.1)			
		Field compaction of upper layer to be 98% MDD obtained from test AS 1289.5.1.1 (Standard Compaction)			
4.19.2	Fill below structural foundations	Field compaction of fill to be 95% MDD obtained from test AS 1289.5.1.1 (Standard Compaction)			
4.19.3	Backfill below structural foundations	Field compaction of backfill (sub-base quality material) to be 95% MDD obtained from test AS 1289.5.1.1 (Standard Compaction)			
4.19.4	Backfill to excavation for structural foundations	Field compaction of fill to be 95% MDD obtained from test AS 1289.5.1.1 (Standard Compaction)			
Notes					
Name					
Signatur	e	Date			

	GROUP 4 - EARTWORKS				
	CHECK SHEE	T 4D – Measurement Records			
Clause	Title	Check	Unit	Y/N	
4.20.1	Measurement	Topographical or level survey needed after			
and	and Payment	completion of clearing and topsoil removal.			
4.22.1	_	This should preferably be a joint exercise.			
4.5	General				
	Excavation				
4.5.1	General	Measurements and levels will be needed to			
		establish records of the horizon where the			
		material in a cutting changes from one type to			
		another.			
		Measurement of materials Class C will be	m ³		
		required if not done as part of GROUP 3 activities			
4.20.1		Separate measurement of pockets of unsuitable	m ³		
		material may be required as work progresses if it			
		is not feasible to calculate unsuitable from the			
		cross section method			
4.6.2	Unsuitable	Measurement of volumes of insitu sub-grade that	m³		
	Material in	are undercut and replaced with selected material			
	Sub-grade	will need recording. Separate records needed for			
		volumes less than 25 m3 for payment under sub-			
1.10	F actoria di San	Clause 23	-		
4.12	Excavation	If there is a risk that excavation may cause			
	for Structural	adjacent buildings, pavements or services may			
	Foundation -	be damaged a pre-condition survey should be			
		made.			
	VVOIKS				
1			1	1	

Notes	
Nama	
Name	
Signature	
Date	

GROUP	GROUP 5 - BASE AND SUB-BASE PAVEMENT COURSES				
LIEUN	SHEEL JA - CI	hecks Required before physical works con	Illence		
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")	
5.2	Materials				
5.2.1	Material Source Assessment	Has the Contractor submitted the material source assessment report at least 10 days prior to planned delivery of material to stockpile or pavement?		Delivery should not commence	
		Does the assessment include an investigation of geological site characteristics and source material properties, and describe the extraction and production operations and plant capacity to process the material?		Instruct that the report to be amended	
		Has the material source been classified into one of the material groups nominated in the Specification and does the assessment show that the material meets all the requirements without addition of imported material?			
		Is the material classification for Base and Sub-base shown on the Drawings or Supplementary Specification? <i>Note: If not indicated the default</i> <i>requirement is Base to be Class 2.1 and</i> <i>Sub-base to be Class 3.2</i>			
5.2.3	Coronous Material	If it is proposed to use coronous material, has a source been approved?			
		processing been approved prior to full scale production?			
		Has the Contractor demonstrated that the material complies with all the specified requirements?			
5.2.4	Cinder or Scoria	Has the Contractor proposed to use scoria and has a source been approved?			
		processing been approved prior to full scale production?			
		Has the Contractor demonstrated that the material complies with all the specified requirements?			
5.3.2	Stockpile	Are lot sizes, number and frequency of tests detailed in a Supplementary Specification?		Construction Supervisor to issue directive	
Notes					
Name Signatur	·····	Date			

GROUP	GROUP 5 - BASE AND SUB-BASE PAVEMENT COURSES				
CHECK	SHEET 5B - (Checks Require During or After Physical Wo	rks		
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")	
5.2	Materials			,	
5.2.2	Material Types	Has imported material been added to a source material?		Further testing will be required	
5.3.2	Stockpile	Are stockpiles located on clear, even, firm, and well drained ground and well indicated as to content?			
		Are separate stockpiles at least 2 metres apart?			
		Are lot sizes, number and frequency of tests detailed in a Supplementary Specification?		Construction Supervisor to issue directive	
5.4	Construct- ion				
5.4.1	Mainten- ance of Sub-grade and Pavement Layers	Has the Contractor adequately maintained the condition of the sub-grade or pavement layer upon which pavement material is to be placed?		Instruct reinstatement measures (Contractor's expense)	
5.4.2	Overlay of Existing Formation	If material is to be added to an existing pavement has the top been suitably scarified?		Instruct depth to be scarified	
		Is the total depth of scarified and added material within the specified layer thickness limits? <i>Note: minimum 75 mm to maximum 250mm</i>			
5.4.4	Moisture Content	Is the moisture content of the pavement material to be compacted at or near to the Optimum Moisture Content?		Add water or dry back before compaction	
5.4.5	Surface Finish	Does the final unbound pavement layer have a uniform surface free from loose or segregated and contaminated areas with course particle slightly exposed? <i>Note: if coronous material is being used the</i> <i>exposure of course particles may not be</i> <i>practicable</i>		Instruct additional brooming, watering and rolling or rip and rework as may be appropriate	
5.4.6	Application of Prime Coat	Have the levels, compaction and surface finish of the base course surface been approved?		Bituminous surfacing cannot commence	

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
5.5	Product Standards			
5.5.1	Horizontal Alignment	Is the location of any point on the pavement within ±50mm of the corresponding point in the contract documents? Note: An unconstrained edge (no kerb, channel or edge strip) will need to be overbuilt slightly to ensure that compaction can be achieved over the carriageway design width. In this circumstance the plus tolerance should be interpreted pragmatically.		
5.5.2	Surface Finish	Do the vertical alignment tolerances comply with the specified requirements?Note:Pavement CoursePrimary Tolerance (mm)3m Straight Edge Deviation Limit (mm)Base Course ± 15 5Sub Course ± 15 8Sub Course ± 15 8		
		Is the crossfall within 0.5% of the specified value? Note: Crossfall is measured within the boundaries of a cross-section element which has a constant fall between any two points more than 2 metres apart, except for portions of cross-sections designed with lesser width, for which sections the crossfall shall be measured between the extreme edges of the section; measurement is transverse to the centre line Does the surface evenness meet the specified requirements?		
5.5.2	Compaction	Have pavements using Type 1 material been compacted to a Characteristic value of 98% MDD obtained from AS 1289.5.2.1 (Modified Compaction)		
		Have pavements using any other material, including coronous, cinder and scoria material been compacted to a Characteristic value of 98% MDD obtained from AS 1289.5.2.1 (Modified Compaction)		

Clause	Title	Check	Y/N	Response if N (default is "issue
5.5.2	Compaction (continued)	Alternatively, for unsealed roads , has compaction to the specified requirements been carried out (and witnessed) <i>Note: Compaction by a vibrating roller or grid</i> <i>roller with a static load per 100 mm width of</i> <i>roll at least 1.75 kN or 7.8 kN respectively,</i> <i>and compaction continued for 12 passes or</i> <i>until movement of the surface under the</i> <i>action of the rollers is negligible</i>		Instruction)
5.5.3	Segregation	Has the particle size distribution of the material in the pavement been shown to comply with the specified requirements? <i>Note: this needs samples taken from the pavement</i>		
5.6	Construct- ion Compliance Testing			
5.6.1	General	Are lot sizes and testing frequency specified in a Supplementary Specification? Note: If not then the Construction Supervisor will have to issue instructions		
5.6.2	Geometrics	Have geometric tolerances been checked at the specified frequencies and found acceptable?		Rework to be instructed
5.6.4	Segregation	Are there visible signs of segregation?		Rework to be instructed

Notes	
Name	
Signature	
Date	

GROUP 5 - BASE AND SUB-BASE PAVEMENT COURSES						
CHECK	SHEET 5C – Laboratory	or Field Tests Required				
clause	Title	Check	Y/N	Satisfactory		
				Test results		
				provided?		
5.2	Materials			·		
	Property to be Tested	Standard Test				
	Sample preparation	AS 1289.1.1				
	Moisture Content	AS 1289.2.1.1				
	Particle Size	AS 1141.11 / AS 1289.3.6.1				
	Distribution					
	Flakiness Index	AS 1141.15				
	Ten Percent Fines	AS 1141.22				
	value & Wet/Dry					
	Strength variation					
	Sodium Sulphate	AS 1141.24				
	Soundness					
	Maximum Dry Density –	AS 1289.5.2.1				
	Sub-base course					
	Maximum Dry Density –	AS 1289.5.2.1				
	Base course					
	Liquid Limit	AS 1289.3.1.1				
	Plastic Limit	AS 1289.3.2.1				
	Plasticity Index	AS 1289.3.3.1				
	Linear Shrinkage	AS 1289.3.4.1				
	Californian Bearing	AS 1289.6.1.1				
	Ratio					
	Crushed Particles	Queensland Transport Test				
		Q215				
	Road Roughness	Queensland Transport Test				
		Q708				
5.6	Construct-ion					
	Compliance Testing					
5.6.3	Compaction	Insitu compaction to be				
		determined by AS 1289.5.3.1				
		(Sand Replacement) or AS				
504		1289.5.8.1.(Nuclear Gauge)				
5.6.4	Segregation	Samples to be extracted from				
		each Lot. Test Using AS				
		1209.3.0.1				
Notes						
Nomo						
Name						

Date

Form 5D Page 1 of 1

	GROUP 5 - BASE AND SUB-BASE PAVEMENT COURSES							
	CHECK SHEE	CHECK SHEET 5D – Measurement Records						
Clause	Title	Check	Unit	Y/N				
5.8	Measurement and Payment	Measured by nominal end area of cross section multiplied by length on centre line.	M3					
5.6	Construct-ion Compliance Testing	The geometric tolerances, except for the surface evenness, shall be checked by a method of random stratified sampling. <i>Note: Surface levels commonly checked by</i> <i>dipping from string lines every 20m, or 10m on</i> <i>sections with super elevation. Records should be</i> <i>maintained till the project has been completed.</i>						
5.8.2	Pavement Courses	Joint survey will be needed to measure the quantity of pavement of any existing road that is to be incorporated into the new road, to be deducted from measured volume						

Notes	
Name	
Signature	
Date	

GROUP 6 – HAND PACKED STONE PAVEMENT						
CHECK	SHEET 6A - CI	necks Required before physical works con	nmence	9		
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")		
6.2	Materials					
6.2.1	Stone	Has the parent rock been approved? Note: Uniaxial Compressive Strength >75MPa Los Angeles Abrasion <25% Sodium Sulphate Soundness <10% loss				
6.2.2	Bedding Material	Has the bedding material been approved?				
6.2.3	Joint filling and Binding Material	Has the joint filling material been approved? Note: material shall be non-plastic, angular, well graded, crushed stone or natural sand which is free from deleterious material and shall have: • Fineness Modulus of sand fraction shall not be less than 1.80.(FM obtained from the sum of the cumulative percentages of aggregate retained on each of the standard sieves ranging from 9.5 mm to 150 micron and dividing this sum by 100) • Fraction passing 75 micron sieve shall not exceed 10% Recommended target grading Sieve Percentage by Designation Percentage by weight passing square mesh sieves 25 mm 100 10 mm 60-100 2.00 mm 40-70 0.425 mm 25-45 0.075 mm 0-10				

Form 6B Page 1 of 2

Project Na	me	
Chainages	From	То

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
6.3	Construct-ion Equipment	Has the Contractor mobilised a 1 ton vibrating roller for primary compaction and a 3 ton vibrating roller for final compaction?		

Notes	
Name	
Signature	
Date	

GROUP 6 – HAND PACKED STONE PAVEMENT					
CHECK	SHEET 6B - (Checks Require During or After Physical Wo	rks	1	
Clause	Title	Check	Y/N	Response if N (default is "issue	
6.2	Materials	Has the parent rock providing the source of stone been approved?			
		Are stones free from vegetation, soft particles and excess clay or any other substance, which is considered deleterious?			
		Are individual large stones approximately 100 to 150mm in size and roughly cubic in shape with uniform texture? <i>Note: Ratios between dimensions of each</i> <i>stone shall be in range of 0.7 to 1.</i>			
6.2.2	Bedding Material	Is the bedding material clean sharp sand or quarry-crushed-dust free from clay coating, organic debris and other deleterious materials?			
6.2.3	Joint filling and Blinding Material	Is the material used to fill the voids between the large and small wedging stones acceptable?			
6.4	Construct- ion Method				
6.4.1	Preparation of the Foundation	Have sufficient setting out pins, pegs and string lines been established to ensure that the final shape of each pavement layer confirms with the Drawings?			
		Is the Sub-base free from deformations, ruts, soft spots or other defects?		Surface to be re-scarified and sufficient new material added to attain the correct shape.	
6.4.2	Shoulder Construct- ion	Are the shoulders being constructed in advance to the thickness indicated in the Drawings and are arrangements for drainage of the roadbase layer (through the shoulder) being incorporated?			
6.4.3	Bedding Layer	Is the bedding layer being constructed with approved material to a compacted thickness of 50-60mm?			
		Is compaction being varied out with $0.8 - 1$ ton rollers operating in a direction parallel to the centre line and working from the edge towards the centre?			

	T :0			
Clause	litle	Спеск	Y/N	Response if
				(default is
				"issue
				instruction")
6.4.4	Planting	Is the larger stone being used on the outer		, , , , , , , , , , , , , , , , , , ,
	and packing	edge and is work proceeding from the edge		
	stone	towards the centre?		
		Note: It is advisable to also place a row of		
		stones along the centre line, before placing		
		the rest of the stones, to control level.		
		Are the stones being tapped firmly into the		
		final position with a hammer such that they		
		bed into the sand or fine aggregate cushion		
		stopos2		
		Note: There should be at least 30mm of		
		bedding under any stone after tapping into		
		place.		
6.4.5	Joint filling	Are large voids between the stones being		
	and blinding	filled with smaller broken stones packed in		
	_	with a hammer and steel rod after a sufficient		
		area of stones has been placed?		
		Is a thin layer of fine graded aggregate filling		
		material being spread and compacted into		
		the remaining voids?		
		Note: An 800kg to 1 ton Vibrating roller is		
		preferable for primary compaction for 6-8		
		2-1 passes to assist the process. Final		
		compaction using a 8-10 ton dead weight or a		
		3 ton vibrating roller for at least 5 passes is		
		recommended		
6.4.6	Finishing	Has the Contractor allowed 10 days for		
	and Curing	drying out and curing, carried out any		
		necessary rework to weak areas, and spread		
		a 10 mm thick layer of granular filling material		
		on the pavement surface before opening the		
0.5		road to traffic?		
6.5	Laboratory	Is the maximum clearance under a 2 metre		
	and Site	straight eage less than 11mm?		
	resung	Is the laver thickness within the tolerance of -		
		5 mm to +15mm of the specified thickness?		
			1	1

Notes	
Name	
Signature	
Date	

Form 6C Page 1 of 1

GROUP	GROUP 6 – HAND PACKED STONE PAVEMENT							
CHECK	CHECK SHEET 6C – Laboratory or Field Tests Required							
clause	Title	Check	Y/N	Satisfactory Test results provided?				
6.2	Materials	Properties of Parent Rock						
6.5	Laboratory and Site Testing	Uniaxial Compressive Strength >75MPa Test AS 4133.4.2 Minimum Frequency: 3 tests per source and 1 per 500m ³ thereafter Los Angeles Abrasion <25% Test AS 1141.23 Minimum Frequency: 3 tests per source and 1 per 500m ³ thereafter						
		Sodium Sulphate Soundness <10% loss Test AS 1141.24 One per source						
		Stope shape and Fractured Faces visual						
		test						

Notes	
Name	
Signature	
Date	

Form 6D Page 1 of 1

Project Na	me	 	
Chainages	From	 To	

	GROUP 6 – HAND PACKED STONE PAVEMENT				
	CHECK SHEE	CHECK SHEET 6D – Measurement Records			
Clause	Title	Check	Unit	Y/N	
6.6	Measurement and Payment	All in rate	m ²		

Notes	
Name	
Signature	
Date	

Form 7A Page 1 of 1

Project Na	me		
Chainages	From	То	

GROUP	7 – REINFORC	ED CONCRETE PAVEMENT		
CHECK	SHEET 7A - CI	necks Required before physical works con	nmence	9
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
7.2	Materials			
7.2.1	Reinforce- ment	Use Check Sheet for GROUP15		
7.2.2	Concrete	Use Check Sheet for GROUP 16		

Notes	
Name	
Signature	
Date	

GROUP 7 – REINFORCED CONCRETE PAVEMENT				
CHECK	SHEET 7B - (Checks Require During or After Physical Wo	rks	
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
7.2	Materials			
7.2.1	Reinforce- ment	Use Check Sheet for GROUP15		
7.2.2	Concrete	Use Check Sheet for GROUP 16		
7.2.3	Load Transfer Dowels	Has a commercially available galvanised dowel bar been submitted for approval?		Make enquiry to Contractor on what dowels will be used
7.3	Construct- ion Equipment	Have all tools and equipment been approved?		
7.4	Construct- ion method	Has a sand bedding layer been constructed in accordance with details on the drawings and finished true to line and level? <i>Note: This to be soaked with sprinkled water</i> <i>prior to concrete pour.</i>		
7.4.1	Reinforce- ment	Has the reinforcement been placed according to the drawings? <i>Note: Default is 200 x 200 mesh in the top of</i> <i>the slab with 40mm cover</i>		
7.4.2	Pavement Joints	Note: If details shown on drawings are different then drawings should be followed instead of specification that follows		
7.4.2.1	Contraction Joints	Is reinforcement continuous across contraction joints with every second bar or mesh strand cut? Note: if reinforcement is not continuous then Contractor must provide minimum 500mm long 16mm diameter deformed bars at 300 mm centres		
		Are contraction joints minimum 10mm deep formed as straight lines in green concrete less than 4 hours old and with a maximum spacing of 2.5 x slab width?		If not then saw cutting could be instructed
7.4.2.2	Construct- ion joints	Are construction joints formed using formwork and of a minimum 25mm deep and 10mm wide?		
		Are load transfer dowels consisting of minimum 400mm long galvanised steel round bar present at 300mm centres?		
		After 28 days curing have joints been filled just above surface level with a mixture of 50%sand and 50% bitumen?		
7.4.3	Concrete	Note: GROUP 16 requirements are applicable		

Clause	Title	Check	Y/N	Response if
				Ν
				(default is
				"issue
				instruction")
		Has formwork ben inspected prior to concrete		
		pour and found to be correctly positioned to		
		line and level, oiled and sturdy?		
		Has formwork and reinforcement been		
		cleaned prior to concrete pour of all		
		woodchips, dust, concrete splashes and		
		other debris?		
		Have planks been fixed prior to concrete pour		
		to allow concrete to be barrowed into position		
		without walking on top of the reinforcement?		
		Is concrete being adequately but not over		
		vibrated using mechanical pokers?		
		Is the ambient temperature less than 36		
		degrees Celsius?		
		Note: No concrete batching or poring if		
		temperature is more than 35 degrees Celsius		
		Has a suitable surface finish been applied by		
		brooming or raking?		
		Is concrete being properly cured?		
		Is curing concrete protected from traffic		
		loading?		

Notes	
Name	
Signature	
Date	

Form 7C Page 1 of 1

GROUP	GROUP 7 – REINFORCED CONCRETE PAVEMENT						
CHECK	SHEET 7C -	Laboratory or Field Tests Required					
clause	Title	Check	Y/N	Response			
7.2	Materials	GROUP 16 to apply					
7.5	Laboratory						
	and Site						
	Testing						
		Slump test for every batch or as directed					
		Test AS 1012.3.1					

Notes	
Name	
Signature	
Date	

Form 7D Page 1 of 1

GROUP 7 – RE	GROUP 7 – REINFORCED CONCRETE PAVEMENT						
CHECK SHEET	Г 7D – Measure	ment Records					
Clause	Title	Check	Unit	Y/N			
7.6	Measurement	All in rate	m ²				
	and Payment						
		Dowels are not specifically mentioned but					
		if not in the Bill of Quantities as a separate					
		item they must be assumed to be included					
		in the m ² rate.					
		If they are a separate item then an agreed					
		record (no of each type) will be useful					

Notes	
Namo	
Marine	
Signature	
Date	

GROUP 8 - BITUMINOUS SURFACING					
CHECK SHEET 8A - Checks Required before physical works commence					
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")	
8.2	Bituminous Prime Coat				
8.2.2	Cut back Bitumen	Have certificates of compliance or test results been submitted to demonstrate compliance of the materials for the prime with AS 2157, AS 2008 and AS 3568 as appropriate?			
8.2.7	Calibration of the Distributor	Has the Contractor supplied a calibration certificate for the proposed distributor that is less than 12 months old?			
8.2.6 and 8.2.8	Mechanical Distributor and Performance of Distributor	Has the mechanical distributor been approved? Note: The Construction Supervisor may require such tests as he considers necessary to check the performance of the distributor.			
8.2.11	Prime Coat Rate	Has the proposed application rate been proposed by the Contractor 7 days prior to commencing any priming work?			
8.3	Bituminous Surface Treatment				
8.3.2	Bituminous Material	Have manufacturer's certificates of compliance or test results been submitted to demonstrate compliance of the materials for the bituminous surfacing with AS 2008 or AS 1160 (emulsion) as appropriate?			
8.3.3	Adhesion Agent	Has the Contractor submitted a proposal for a proprietary adhesion agent, together with written evidence of the successful use of such additive, prior to purchasing?			
8.3.4	Aggregates	Has the Contractor submitted test results to demonstrate compliance with AS 2758.2? Note: The Specification does not require the Contractor to submit samples to the Construction Supervisor for independent testing and it does not specify a frequency for repeat testing of materials in stockpile but both measures are considered to be good practice. Ensuring that aggregates routinely comply with the specified requirements is an essential aspect of successful bituminous surfacing work.			

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
8.3.8	Plant and Equipment	Has the Contractor submitted details of the proposed equipment which demonstrates that it meets the requirements of this sub- clause of the Specification? <i>Note: Although not specified it is common</i> <i>practice to require 2 rollers to mitigate the</i> <i>risk of a mechanical breakdown</i>		
8.3.10	Application Rate	Has the Contractor submitted for approval the details of the proposed application rate of bituminous binder material and cover aggregate at least seven (7) days prior to any sealing works commencing? Note: The application rate of bituminous binder material and cover aggregate shall be determined by the Contractor using the Update of the Austroads Sprayed Seal Design Method (AP-T68-06) and Update of Double / Double Design for Austroads Sprayed Seal Method (AP-T236-13) and Towards Incorporating Heavy Vehicles into the Austroads Sprayed Seal Design Method (AP-T260-14). The Contractor shall provide full design calculations including details of any assumptions		

Notes	
Name	
Signature	
Date	

GROUP 8 - BITUMINOUS SURFACING				
CHECK	SHEET 8B - Ch	hecks Require During or After Physical Wor	rks	Γ
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
8.2	Bituminous Prime Coat			
8.2.2	Cut back bitumen	If a manufactured product is to be used is it AMC1 cutback bitumen complying with AS 2157?		
		If the prime material is being prepared in the field do the bitumen and cutter comply with AS 2008 and AS 3568 respectively?		
8.2.3	Blotter Material	Is the blotter material clean dry coarse sand or stone?		
8.2.4	Measuring Road Temperature	Is the Contractor taking a road surface temperature reading at regular intervals? <i>Note: The Specification forbids spraying if</i> <i>the temperature is below 18 degrees</i> <i>Celsius This is a rare occurrence in Vanuatu</i> <i>so this requirement might be waived on</i> <i>most occasions</i>		
8.2.5	Base Course Surface	Has the surface of the base course, to a distance of 300 mm beyond the area to be primed, been swept free of loose stones, dust, dirt and foreign matter so as to uncover but not dislodge the course aggregate? Note: This is a hold point and no prime is to be placed until the Construction Supervisor has signed off on the approval of the Basecourse		This is a Hold Point
8.2.6 and 8.2.8	Mechanical Distributor and Performance of Distributor	Has the mechanical distributor been approved?		
8.2.9	Hand Spray Equipment?	Has the Construction Supervisor given consent for any use of hand spray equipment? Note: Use of a hand lance is prohibited except for small areas where use of a mechanical distributor is impractical		
8.2.10	Length to be sprayed	Has the length of the surface to be sprayed by each run of the distributor been measured and marked on the ground and the start and finish points protected with strips of Kraft paper?		
8.2.11	Prime Coat Rate	Has the proposed spray rate been approved?		

Project Name					
Chainages	FromTo				

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
8.2.12	Width of Primed Area	Is the width of the primed area 150mm wider on each side than the width to be sealed and are the edges of the primed area within ±75mm from the specified lines?		
8.2.13	Optimum Temperature	Is the temperature of the prime within 35 to 55 degrees Celsius?		
8.2.14	Application of Prime Coat	Is there an overlap of 200mm between adjacent runs of prime? <i>Note: Where blotter is applied space should</i> <i>be left at the end of the run to allow for this</i> <i>overlap</i>		
8.2.15	Adjacent Trees and Structures	Are adjacent kerbs, trees and structures protected from splatter?		
8.2.16	Traffic restrictions	Is the prime being kept free of traffic and allowed to penetrate for 4 hours before blotter is applied?		
8.3	Bituminous Surface Treatment			
8.3.2	Bituminous Material	Has the bituminous material proposed for use been approved?		
8.3.3	Adhesion Agent	Has a proprietary product for the adhesion agent been approved?		
8.3.4	Aggregates	Have aggregates been tested and found to comply with AS 2758.2?		
8.3.5	Aggregate Size	Are the aggregates the correct size for the layer under construction as shown on the drawings? Note: If size is not shown on the drawings then the default is nominal 14mm aggregate for a single seal and 14mm followed by 7mm for a double seal		
8.3.6	Aggregate Stockpiles	Are aggregates stockpiled appropriately with separate stockpiles for each different size of aggregate? Note: Stockpile areas cleared and drained; 15m apart; surfaced with 100mmm stone if appropriate; material stockpiled 1m high with 1:1 side slopes		
8.3.7	Pre-coating of Aggregates	Have aggregates been pre-coated using a suitable method? Note: coating to consist of distillate with 10% bitumen and 1% adhesion agent applied at a rate of 6-12 litres per m ³ of aggregate		

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
8.3.9	Surface Preparation	Has the surface of the Basecourse been adequately prepared by removing loose stones and dirt from the surface using a power broom or blower, but without the removal of stones embedded in the pavement? Note: Sweeping to extend at least 200 mm beyond each edge of the area to be sprayed.		
8.3.10	Application Rate	Have the application rates for bitumen and cover material been approved? Note this is a hold point		Contractor shall not proceed until written approval is
8.3.11	Spaying Temperature	Is the temperature of the bitumen between 165 and 185 degrees Celsius?		
8.3.12	Area to be sprayed	Is the area to be sprayed limited to that which can be covered with aggregate at the specified rate within 15 minutes of the time of spraying?		Reduce the area
8.3.13	Spaying	Are weather conditions suitable and will spaying commence and finish on a protective strip of paper or other approved surface for at least the full width to be sprayed?		
8.3.16	Traffic Restrictions	Are suitable traffic management measures in place to prevent traffic passing over the working area during the application of bituminous material and cover aggregate and during initial rolling?		
8.3.14	Cover aggregate supply	Is sufficient cover aggregate ready in trucks at the site of the work to provide the full cover for the area to be sprayed?		
		Was the whole of the sprayed area covered with aggregate within 15 minutes of spraying?		
		Has the aggregate been spread to give a uniform and complete coverage?		
8.3.15	Rolling	Did rolling commence as soon as the aggregate had been spread and continue for a sufficient duration? Note: Minimum of 1 hour per 1200 litres of bitumen or until aggregate is predominantly aligned so that the ALD is vertical.		

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
8.3.16	Traffic Restrictions	Are approved signs in place to assist speed control when traffic is allowed to pass over the area of work? <i>Note: Signs bearing the words "wet bitumen" and "20km/h" shall be erected at appropriate locations not more than 300</i> <i>metres apart</i>		
8.3.17	Monitoring	Is the Contractor monitoring the completed work and was all loose stone removed 7 days after the completion of the rolling? <i>Note: Contractor and Supervisor to</i> <i>consistently check the treated surface for</i> <i>any tendency to softening or bleed and</i> <i>these areas should be attended to by</i> <i>addition of small quantities of additional</i> <i>aggregate evenly spread.</i>		

Notes	
Name	
Signature	
Date	

GROUP 8 - BITUMINOUS SURFACING						
CHECK	SHEET 8C -	Laboratory or Field Tests Required				
clause	Title	Check	Y/N	Satisfactory Test results provided?e		
8.2.2	Cut Back Bitumen	AS 2157 Cut Back Bitumen AS 2008 Residual Bitumen for Pavements AS 3658 Oils for reducing the viscosity of residual bitumen for pavements				
8.3.2	Bituminous Material	AS 2008 Residual Bitumen for Pavements AS 1160 Bituminous emulsions for the construction and maintenance of pavements				
		Note: It is common practice to accept certificates of compliance from reputable manufacturers which contain test certificates from accredited laboratories. If testing is required these Standards provide information on sampling methods and material properties that need to be established.				
8.3.4	Aggregates	AS 2758.2 Aggregates and rock for engineering purposes, Part 2: Aggregates for sprayed bituminous surfacing <i>Note: Defines three classes of aggregate,</i> <i>A, B, C depending on traffic volumes. For</i> <i>less than 600 vehicles per lane per day,</i> <i>Class C applies.</i> <i>(AS 2758.2 contains some choices that</i> <i>should be clarified in the Works</i> <i>specification. Currently the PWD Standard</i> <i>Specification does not include any specific</i> <i>requirements for sealing aggregates but</i> <i>these could be included in a Supplementary</i> <i>Specification).</i>				
		AS 2758.2 Makes cross reference to other Australian Standards:				
	1141.3.1	Method 3.1: Sampling—Aggregates				
	1141.11.1	Method 11.1: Particle size distribution— Sieving method				
	1411.11.2	Method 11.2 Particle size distribution for vision sizing systems				
	1141.15	Method 15: Flakiness index				
	1141.20.1	Method 20.1: Average least dimension— Direct measurement (nominal size 10 mm and greater)				
	1141.20.2	Method 20.2: Average least dimension— Direct measurement (nominal sizes 5 mm and 7 mm)				
Clause	Title	Chack	\//N I	Catiofactory		
Clause		L UNECK	Y/N	Satistactory		

Form 8C Page 1 of 2

Project Na	me
Chainages	FromTo

			Test results provided?
1	141.20.3	Method 20.3: Average least dimension— Calculation (nomograph)	
1	141.22	Wet/dry strength variation	
1	141.23	Los Angeles value	
1	1141.24	Aggregate soundness–Evaluation by exposure to sodium sulphate solution	
1	1141.30.1	Method 30.1: Coarse aggregate quality by visual comparison	
1	1141.32	Method 32: Weak particles (including clay lumps, soft and friable particles) in coarse aggregates	
1	1141.50	Method 50: Resistance to stripping of cover aggregates from binders	

Notes	
Name	
Signature	
Date	

GROUP 8 - BITUMINOUS SURFACING						
	CHECK SHEE	T 8D – Measurement Records	1			
Clause	Title	Check	Unit	Y/N		
8.2.17	Measurement of Prime Coat	All in rate Note: There is no variation in the rate to accommodate any variation to the spray rate. The variation in the spray rate is a Contractor risk. It is however usual practice to check the application rate in the field by measuring the depth in the distributor tanker with a dipstick before and after each run to calculate total application against the area sprayed	m ²			
8.2.18	Measurement of Blotter Material	When shown as a separate item in the BoQ Note: If there is no separate item then blotter is to be taken as included in the rate for prime	m ²			
			2			
8.3.18	Measurement of Bituminous Surfacing	All in rate covering bitumen, cover aggregate, adhesion agent and pre-coating material.	m²			
8.3.19	Conformance and Non- conformance	Note: To calculate the conformance standard it will be necessary to check the total application by measuring with a dipstick the distributor tanker before and after each run to calculate total application against the area sprayed. It will also be necessary to take the temperature of the hot bitumen in the tanker.				
				1		

Notes				
Namo				
Name				
Signature				
_				
Date				
GROUP	9 - DRAINAG	Ε		
---------	---------------------------------	--	------	---
CHECK	SHEET 9A - (Checks Required before physical works co	mmer	ice
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
9.1	General	Do the drawings show all initially planned drainage lines with sufficient details for construction i.e. alignment and levels, type and size?		
9.2	Materials			
9.2.1	Reinforced Concrete Pipes	Has the Contractor demonstrated satisfactorily that RC pipes that have or will be brought to the Site have been manufactured in conformance to AS 4058?		Do not accept until compliance has been demonstrated
		Has testing in accordance with AS 4058 been carried out at the place of manufacture in the presence of the Construction Supervisor? Note: if precast pipes are being imported and the manufacturer has a QA system that is accredited to ISO 9004 standard or uses a third party certification scheme, then consideration might be given to relaxing this requirement. AS 4058 allows a third part product certification scheme Are pipes delivered to Site the correct type and class? Note: Default is rubber ring spigot and		
		Are pipes delivered to Site free from defects and damage?		Reject or Instruct testing or other measures in regard to damaged or repaired pipes
9.2.3	Corrugated Steel	Has the Contractor satisfactorily demonstrated that corrugated steel pipes that have or will be brought to the Site have been manufactured in conformance to AS 2041?		Do not accept until compliance has been demonstrated
9.2.3.1	Nestable and Boltable	Have plates been shop rolled to increase the vertical dimension by 5%		Query this requirement
9.2.3.2	Helical lock seam	Has the Contractor satisfactorily demonstrated that helical lock seam pipes that have or will be brought to the Site have been manufactured in conformance to AS 1761?		Do not accept until compliance has been demonstrated
		Are there any welded joints in the pipes?		

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
9.2.4	Precast Concrete Box Culverts	Has the Contractor satisfactorily demonstrated that precast concrete box culverts that have or will be brought to the Site have been manufactured in		Do not accept until compliance has been demonstrated
		conformance to AS 1597?Has testing in accordance with AS 1597been carried out at the place ofmanufacture in the presence of theConstruction Supervisor?Note: if precast concrete culverts arebeing imported and the manufacturer hasa QA system that is accredited to ISO9004 standard or uses a third partycertification scheme, then considerationmight be given to relaxing thisrequirement. AS 527 allows thesemethods of product compliance		
		Are the date of manufacture and the name of trademark of the manufacturer marked on each culvert section?		
		Are box culverts delivered to Site the correct class?		
		Are pipes delivered to Site free from defects and damage?		Reject or Instruct testing or other measures in regard to damaged or repaired pipes
		If a Contractor's design is required for an insitu base slab, has this been provided and approved?		
		Are the proposed lifting arrangements considered to be satisfactory?		
		If the whole of the box culvert is to be manufactured on the Site, have the required design details and method statement been provided (at least two weeks prior to proposed start of manufacture)		
9.4.5	Placing Precast Concrete Box Culvert	Have installation instructions been provided by the manufacturer or shown on drawings?		
9.3	Excavation and Bedding	Has the method for disposal of surplus excavated material been approved?		
		Is trench construction method required?		

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
9.4	Placing	Have all fasteners for bolted corrugated metal structures been shown to comply with AS 1112?		
9.4.3.1	Corrugated Steel Pipe - Helical Lock Seal	Have pipes and coupling bands been given hot dipped bitumen coating as part of the manufacturing process?		
		Have the ends of helical lock seal pipes been re-rolled with 4 annular corrugations of 68mm where joints will be made on site?		
9.7	Taking Up and Stacking	Are any instructions required for taking up existing culverts?		
9.10	Subsoil Drainage	Has the Contractor satisfactorily demonstrated that sub-soil drains that have or will be brought to the Site have been manufactured in conformance to AS 2439.1?		Do not accept until compliance has been demonstrated
		Are construction details and locations shown on drawings? Type A construction is the default if details not shown on drawings.		Instruct locations if necessary.
9.11	Lined Drains			
9.11.2	Stone pitched Lined Drains	Is rock proposed for the work suitable? Note: Sound, durable stones with size not less than .001 m3 with least dimension of 75mm		
9.11.4	Precast Concrete Lined drains	Has the Contractor submitted details of formwork and casting procedures for precast concrete units for prior approval? <i>Note: Manufacture should not commence</i> <i>until procedures have been approved</i>		
9.13	Kerbs, Channels and Edge Strips			
9.13.3	Cast Insitu by extrusion Machine	Has the Contractor provided a satisfactory test section?		
Notes				
Name				
Signatu	re			

GROUP	GROUP 9 - DRAINAGE				
CHECK	SHEET 9B - CI	necks Require During or After Physical Wor	rks	-	
Clause	Title	Check	Y/N	Response if	
				N (defeuilt is	
				instruction")	
9.2.2	Mortar for	Are the constituents and moisture content of			
	Joints	mortar for jointing satisfactory?			
9.2.3.2	Helical lock	Have any/all field cut ends been treated as			
	seam	specified?			
9.3	Excavation	Has excavation been carried out to the			
	and Bedding	correct line and levels?			
		Is width of trench acceptable?			
		Note :(Minimum of curvert width plus			
		Has the foundation material in trench			
		bottom been inspected prior to placing of			
		bedding material and pipes?			
		Note: It would be useful if this was a Hold			
		Point			
		If foundation material is suitable, has it been			
		compacted satisfactorily?			
		If foundation is rock has additional 150mm			
		been excavated?			
		Has this additional rock excavation been			
		material2			
		If foundation material (other than rock) is			
		unacceptable has the depth (and width) of			
		additional excavation been instructed?			
		Note: width to be 1.5 x culvert diameter or			
		span			
		Is bedding material acceptable and has it			
		been adequately shaped?			
		Note: Minimum depth 75mm plus one tenth			
0.4	Placing	or the curvert diameter for shaping		<u> </u>	
9.4 0 <u>/</u> 1	Reinforced	ls installation progressing from the outlet			
0.4.1	Concrete	end towards the inlet end and are socket			
	Pipe	ends facing in the upstream direction?			
		If there is a 'top side has this been placed			
		correctly?			
		Are conditions suitable for mortar jointing to			
		commence?			
		If the culvert has more than one barrel are			
		they spaced in accordance with the			
		Urawing?		<u> </u>	
		settlement and damage?			
9.4.2	Corrugated	Is installation progressing from the inlet end			
0.1.2	Steel Pipe -	towards the outlet end with bottom sheets			
	Nestable	one sheet ahead of full circle construction?			

Project Na	me	 		 	 	
Chainages	From	 	.To.	 	 	

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
		When sections are added are they outside the one already placed?		
		Are longitudinal joints in the same horizontal plane and circumferential joints staggered?		
		Have joints been covered with a suitable geotextile cloth prior to commencing backfilling?		
		If the culvert has more than one barrel are they spaced in accordance with the drawing?		
		Have pipes been placed without undue settlement and damage?		
9.4.3	Corrugated Steel Pipe Bolted	Is work progressing from the outlet end with all bottom plates being placed first?		
9.4.3.2	Corrosion Protection	Have bottom plates been painted on the outside before placing?		
9.4.3	Corrugated Steel Pipe Bolted	Is placing of side and top plates commencing from the inlet end and with side plate only sufficiently ahead of top plates to ensure stability?		
		Have bolts been left untightened until all plates ae assembled?		
		After all plates are assembled have all bolts been inserted and tightened then rechecked?		
		If the culvert has more than one barrel are they spaced in accordance with the drawing?		
9.4.3.1	Corrugated Steel Pipe- Helical Lockseal	Is installation according to AS 1726? Note the following requirements which differ from other parts of the Standard Specification (i) If foundation material is unsuitable trench width to be 2 x diameter (ii) If rock foundation extra excavation is the lesser of diameter/4 or 250mm (iii) loose (iv) granular material of 12 mm maximum aggregate size shall cover the shaped bedding of a firm foundation to a depth sufficient to allow the corrugations to become filled with the material.		

Project Na	ne	
Chainages	FromTo	

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
		Have all field cut ends been prepared and painted as specified?		
		Have joints been covered with a suitable geotextile prior to backfilling?		
		If the culvert has more than one barrel are they spaced in accordance with the drawing?		
		Have pipes been placed without undue settlement and damage?		
9.4.3.2	Corrosion Protection of Corrugated Steel Pipes	Has a suitable protective coating been applied?		
9.4.5	Precast Concrete Box Culverts	Are the manufacturer's instructions or other approved installation method been followed?		
		Has a gap of 15mm been maintained between adjacent cells?		
		Has the gap been filled with approved filler?		
		Are mortared joints protected from the sun for 48 hours?		
9.5	Backfilling	Has approval been given for backfilling to commence? Note: It is a hold point for inspection and approval to be given before backfill commences		
		Is the backfill material suitable? Note: Granular material; Maximum size 75mm; at least 50% <2.36 mm; no boulders or organic material; maximum PI of 12.		
		Is the backfill being placed in layers not exceeding 150mm?		
		Is the backfill being placed on both sides of the culvert at the same time with a maximum difference in level of 150mm?		
		Is material under the haunches and near the sides being compacted with hand held equipment?		
		Is compaction being tested and meeting the required standard?		
		Has adequate cover material been placed above the top of the culvert? Note 300mm above top and one diameter either side or half the wall height for embankment condition and full depth of trench for trench condition.		

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
		Has any damage occurred during backfilling?		Instruct Contractor to submit proposal for repairs, or reject
9.7	Taking up and Stacking Culverts	Have culverts shown on drawings or instructed to be taken up been stacked in approved locations?		
		Have such culverts that are not re-laid been transported to the Construction Supervisor's office compound?		
9.10	Sub-Soil Drainage	Is width of trench 300mm and depth between 650mm and 1500mm?		
		and compacted on a uniform grade?		
		Has placing of bedding and pipe laying been approved before backfilling commences?		
		Does backfill material meet the specified requirements for grading? Note: Table of grading requirements is in Specification for Type A and Type C construction. Type B is 100% passing 19mm and 98% larger than 1.5 x slot size.		
		Has backfill been satisfactorily compacted? Note: 90% of MDD obtained from Standard Compaction method		
0.44				
9.11.1	General	Have lined drains been constructed to lines, grades and cross sections shown on the drawings using materials shown on drawings or materials directed by the Construction Supervisor?		
9.11.3	Cast In-situ Concrete Lined Drains	Is formwork being used to maintain line and level?		
		Is the work within tolerances? Note: Tolerance of formwork should be checked before concrete is poured. Requirement is ±25mm from a design surface and maximum 5mm deviation over a 3m straight edge.		Instruct that formwork be placed again to meet tolerances
		Does the concrete (and reinforcement if used) meet the requirements of clause 16 (and 15)?		
		Is the concrete grade 25?		

Project Name			
Chainages	From	То	

Clause	Title	Check	Y/N	Response if N Default is
				"Issue instruction")
9.11.4	Precast Concrete lined drains	Have units been manufactured using Grade 30 concrete and according to approved procedures with tolerance ± 3mm?		
9.12	Drainage Structures	Have all structures been inspected and constructed to the dimensions shown on the drawings?		
		Have the requirements of Group 11, 15 and 16 been fulfilled?		
9.3	Construction of Concrete Kerbs, Channels and Edge Strips			
9.13.8	Bedding	If the product is not based on a pavement layer has the bedding been prepared as stipulated? Note: Sub-base quality material of 75mm compacted thickness on top of prepared subgrade. Compaction to be 90% MDD from Standard Compaction Test AS 1289.5.2.1		
9.13.1	General	Are kerbs constructed to lines and levels shown on the drawings?		
		Has the strength of the concrete in precast kerbs been shown to be Grade 25?		
9.13.3	Cast Insitu by extrusion Machine	Has the Contractor provided a satisfactory test section which was approved by the Construction Supervisor?		Contractor is required to provide a test section
		Is work free from voids and honey combing and with a steel trowel finish?		If a suitable standard cannot be achieved instruct the use of formed concrete
		Has the concrete been mixed for Grade 30 and shown to have strength for Grade 25?		
9.13.5	Construction Joints	Have construction joints been formed as required? Note: Contraction joints formed at max 5m intervals with grooves on all exposed surfaces at right angles to surface, 40 mm deep and max 6mm wide Expansion joints at 40m intervals with 6mm bitumen impregnated fibre board. Must line up with any joints in adjacent structures		

Form 9B Page 6 of 6

Project Na	ne
Chainages	FromTo

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
9.13.6	Curing	Is all insitu concrete being cured in a satisfactory manner?		
9.13.7	Tolerances	Are alignments of kerbs and channels smooth with tolerance of ±10mm?		

Notes	
Name	
Signature	
Date	

GROUP 9 DRAINAGE				
CHECK	SHEET 9C – Labo	ratory or Field Tests Required	-	
clause	Title	Check	Y/N	Satisfactory Test results provided?
9.5	Backfilling	The backfill material shall be selected granular material free from lumps and vegetable matter and boulders or stone of greater size than 75 mm and having at least 50% retained on 2.36 mm sieve.		
		The Plasticity Index of backfill material shall not exceed 12% when tested in accordance with AS 1289.3.3.1.		
		Backfill to be compacted to 98% of the Maximum Dry Density determined by AS 1289.5.1.1 (Standard Compaction)		
		Backfill within 300 mm of the underside of the sub-base level shall be compacted to 100% of the Maximum Dry Density determined by AS 1289.5.1.1 (Standard Compaction)		
		The density of the material shall be determined by AS 1289.5.3.1 (Sand Replacement) or AS 1289.5.8.1 (Nuclear Gauge)		
9.10	Subsoil drains	Grading requirements for backfill for Type A and C to meet table in Specification		
		Filter material in sub-soil drainage shall be compacted to a density of at least 90% of the Maximum Dry Density as determined by AS 1289.5.1.1. (Standard Compaction). The density of the material shall be determined by AS 1289.5.3.1 (Sand Replacement) or AS 1289.5.8.1.(Nuclear Gauge)		
		Note: Sand Replacement Test unlikely to be practicable in a 300mm trench		
9.11	Lined Drains			
9.11.3	Cast insitu concrete lined drains	Concrete will need testing pursuant to Group 16. Checks may be needed on constituent materials, slump and cylinder strengths to demonstrate Grade 25 concrete		
9.11.4	Precast concrete	Witnessing of pre-cast concrete unit		
	lined drains	production and some random		

Form 9C Page 1 of 2 Project Name..... Chainages From......To.....

		independent materials and concrete testing may be advisable		
clause	Title	Check	Y/N	Response
9.13.3	Cast Insitu by extrusion Machine	Concrete strength of 25MPa required. Random verification testing is recommended		
9.13.8	Preparation and Bedding	Compaction testing of bedding to 90% MDD using AS 1289.5.2.1		

Notes	
Namo	
Name	
Signature	
Date	

Form9D Page 1 of 1

	GROUP 9 DRAINAGE			
	CHECK SHEE	T 9D – Measurement Records		
Clause	Title	Check	Unit	Y/N
9.11.6	Measurement and Payment	Linear metre for different types of drain	m	
		Agreed records may be required for the following additional items if they are shown separately in the Bill of Quantities		
		Unsuitable material in trench foundation	M ³	
		Rock volumes if excavation in rock has a separate pay item	M ³	
		Excavation for inlets and outlets	M ³	
		Lengths of inlet and outlet channels	М	
		Lengths of existing culverts removed	М	
		Length and location of sub-soil drains	М	

Notes	
Name	
Signature	
Date	

GROUP 10 – ROAD FURNITURE AND MARKINGS				
CHECK	<u>SHEET 10A -</u>	Checks Required before physical works of	omme	ence
Clause	Title	Check	Y/N	Response if N Default is " issue instruction")
10.1	Road Signs			
	General	Do the drawings and/or Schedules show all the road signs that will be required and their locations? <i>Note: AS 1742.2 contains information on</i> <i>the positioning of signs</i>		Prepare and issue a schedule
10.1.2	Standard	Has the Contractor shown satisfactory evidence that all signs that have or will be delivered to the Site are manufactured in accordance with AS 1743? Not: The Standard provides graphics, layout and size requirements together with an abridged materials and manufacturing specification		
		Do retroreflective materials conform-in colour and Grade to AS 1743 Appendix C for Class 2 materials and with AS 1906.1? Note: There is no Appendix C or mention of Class 2 materials in AS 1743. This appears to be an error in the Specification		
		Are details of sign construction, including sign materials, stiffeners, posts, fasteners and foundations shown on drawings or in the Supplementary Specification?		Construction Supervisor may need to issue additional information
10.2	Guard Rails	Are the locations and details of guard rails shown on the drawings and/or schedules?		Construction Supervisor may need to issue additional information
10.2.2	Timber posts for guardrail	If the Contractor intends to use timber posts, is the timber of an acceptable type and strength group and has it been pressure treated with preservative? Note: Strength group SD3 to AS 2878. Pressure treated with chrome arsenic solution with retention 0.032 gram per cubic centimetre		Approval needed prior to construction
10.2.3	Steel Beam Guard Rail	Has the Contractor demonstrated that guard rails that have or will be delivered to the site meet the specified requirements? <i>Note: Guard Rails to be Armco Flexbeam</i> <i>or similar approved.</i> <i>Surface treatment to AS 1627.4 of 1627.5</i> <i>then galvanising to AS 4680</i>		

Clause	Title	Check	Y/N	Response if N Default is " issue instruction")
10.2.3	Steel Beam Guard Rail (continued)	Has the proposed fasteners including galvanised nuts bolts and washers been approved? <i>Note: Materials to meet requirements of</i> <i>AS 111.1, 1111.3, AS 1237 and AS 1214</i>		
10.3	Road Edge Marker Posts	Are the locations and details of road edge guide markers shown on the drawings and/or schedules?		Construction Supervisor may need to issue additional information
		Has the Contractor demonstrated that edge marker posts that have or will be delivered to the site meet the specified requirements?		
10.4	Pavement Markings			
10.4.2	Pavement Marking Type	Has the Contractor demonstrated that the paint will be in accordance with AS 4049.3?		
		Has the Contractor demonstrated that the glass beads will be in accordance with AS 2009?		

Notes	
Name	
Signature	
Date	

GROUP 10 – ROAD FURNITURE AND MARKINGS				
CHECK	SHEET 10B - 0	Checks Require During or After Physical We	orks	
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
10.1	Road Signs	Note: There are no construction requirements set out in the Specification. Details of signs for construction purposes should be shown on drawings or supplementary specification and be checked on site for compliance. (Sign and post materials, stiffeners, height above ground, fasteners, foundation details)		
		Are details of sign construction, including sign materials, stiffeners, posts, fasteners and foundations shown on drawings or in the Supplementary Specification?		Construction Supervisor may need to issue additional information
		Have signs been constructed according to the required details?		
10.2	Guardrail Timber Posts	If the Contractor intends to use timber posts, has the proposed timber been approved? Note: Strength group SD3 to AS 2878. Pressure treated with chrome arsenic solution with retention 0.032 gram per cubic centimetre		Installation not to proceed without prior approval of the timber
10.2.3	Steel Beam Guard Rail	Have field cut ends been treated in accordance with the specification? Note. Wire brushing then painting with zinc primer to AS 3750.9 and 2 coats zinc silicate paint to AS 3750.15		
		Have bolts nuts and wasners been		
10.2.4	Erection of steel beam guard rail	Have posts been set to line, level and correct spacing, including accommodation for any splayed ends?		
		Are posts and block out pieces erected with concave ends facing away from oncoming traffic?		
		Have laps in beam sections been made so that the exposed end of the beam faces away from the direction of oncoming traffic?		

Project Name		
Chainages	FromTo	

Clause	Title	Check	Y/N	Response if
				N
				(default is
				"ISSUE
		Are holte at eletted expansion jointe leasted		instruction")
		in the centre of the slot and not so tight as		
		to prevent sliding?		
		Are all other holts as tight as possible?		
10.3	Road Edge	Are the road edge marker posts the type		
10.5	Marker Posts	shown on the Drawings and are they		
		positioned and spaced as shown on the		
		Drawings?		
10.4	Pavement			
	Markings			
10.4.4	Pavement	Is the surface clean and dry and in suitable		
40.40	Condition	condition for application of paint?		
10.4.2	Pavement	Have the type of paint and glass beads		
40.4.0	Marking Type	been approved?		
10.4.3	Paint for	Is the paint white except at bridge hazard		
	Road	Markings where it is yellow type 2?		
	Marking	AS4049.3		
		Is paint applied with a dry thickness		
		(excluding glass beads) of 0.3 mm for		
		longitudinal lines and 0.2mm for transverse		
		lines?		
		Note: AS 4049.3 states that a minimum wet		
		film thickness of 0.5 mm is needed for Type		
		D beads. For type B beads optimum wet		
40.45	Deflect'	tilm thickness is 300 to 400 g/m2.		
10.4.5	Reflective	Have the type of beads to be used been		
	Glass Deaus	approved?		
		Type D (longitudinal lines) and 200 g/m2 for		
		Transverse lines?		
		Note: There is no simple way to check		
		retention so it is suggested that the rate of		
		application is checked as being 500g/m2 for		
		Type D and 300 g/m^2 for Type B which is		
		the recommended application rate in AS		
		2009 for a smooth substrate.		

Notes	
Name	
Cignosture	Dete
Signature	Date

GROU	GROUP 10 – ROAD FURNITURE AND MARKINGS						
CHECK	CHECK SHEET 10C – Laboratory or Field Tests Required						
clause	Title	Check		Response			
10.4.3	Paint for Road Markings	If it is necessary to test paint then test methods are described in AS 4049.3.					
		To measure paint film thicknesses use wet or dry film thickness gauges as appropriate, capable of confirming that the specified film thickness has been achieved. Suitable methods are described in AS 1580.107.3, or AS 1580.108.1. Wet film mass and dry film mass may also be used to determine paint film thickness, using the methods in AS 1580.107.1 or AS/NZS 1580.107.2.					

Notes	
Name	
Signature	
Date	

	GROUP 10 – ROAD FURNITURE AND MARKINGS						
	CHECK SHEE	CHECK SHEET 10D – Measurement Records					
Clause	Title	Check	Unit	Y/N			
10.1.3	Measurement and Payment	If signs vary considerably in size it is envisaged that the Bill of Quantities will provide for different rates for differing sizes	no.				
10.2.5	Measurement and Payment (Guard rails)	Note that measurement is centre to centre of end posts, so any laps and overshoot beyond end posts is not measured	m				
10.3	Road Edge Marker Posts	Not stated but logically by number	No.				
10.4.6	Measurement and Payment (Pavement Markings)	Only covers actual length measured in metres. If the road markings require lines of various widths and Arrows or Letters then separate provision must be made in the BoQ.	m				
				1			

Notes	
Name	
Signature	
Date	

GROUP 11 – MASONARY FOR STRUCTURES							
CHECK	CHECK SHEET 11A - Checks Required before physical works commence						
Clause	Title	Check	Y/N	Response if N Default is " issue instruction")			
11.1	Stone Pitching	Is the proposed stone sound and durable with a minimum dimension of 150 mm and a maximum of 450 mm?					
11.2	Rock walling						
11.2.1	General	Does the proposed rock consist of sound durable stones, of not less than 0.016 cubic metres in volume, at least 150 millimetres in vertical dimension and 300 millimetres in both horizontal dimensions?					
11.2.2	Cement Grouted Rock Walling	Does the proposed rock consist of sound durable stones, of not less than 0.016 cubic metres in volume, at least 150 millimetres in vertical dimension and 200 millimetres in both horizontal dimensions <i>Note: Specified Volume is inconsistent</i> <i>with dimensions. It is suggested that the</i> <i>dimensions take precedence as it is</i> <i>intended that smaller sizes of stone can be</i> <i>used in cement grouted walls as</i> <i>compared to dry stone walls</i>					

Notes	
Name	
Signature	
Date	

GROUP 11 – MASONARY FOR STRUCTURES							
CHECK	CHECK SHEET 11B - Checks Require During or After Physical Works						
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")			
11.1	Stone Pitching						
11.1.1	General	Do stones have a minimum dimension of 150 mm and a maximum of 450 mm?					
		Are stones being roughly dressed?					
11.1.2	Mortar for grouting	Does mortar for stone pitching consist of 1 part cement to two parts sand and just sufficient water to be of a workable consistency?					
11.1.3	Laying	Is the surface on which stones are to be placed stable, and if it is embankment fill has it been well compacted?					
11.1.4	Cement Grouting	Is a cut off wall required and is it being constructed according to drawings or as described in this clause? <i>Note: Cut Off Wall is required if foundation</i> <i>material is erodible. Minimum wall thickness</i> 450 mm. Minimum depth not specified but 450 mm suggested. Fill trench with mortar to 60% of the maximum stone dimension. <i>Place stones. Repeat till trench filled. Place</i> <i>stone pitching in tight contact with wall.</i> Are the stones well bedded in mortar with additional mortar trowelled to a depth of 60 percent of the maximum thickness? Are the larger stones used as toe stones at edges or in aprons and do the stones fit together closely and present an even top surface? Are weep holes included? Is mortar being well rodded into the voids between stones to a depth of at least 75mm from the surface? Is the grouted stone being kept damp for 48					
		hours after placing					
11 2	Rock Walling						
11.2	General	Is the stone sound and durable not less					
11.2.1	General	than 0.016 cubic metres in volume, at least 150 millimetres in vertical dimension and 300 millimetres in both horizontal dimensions? <i>Note: smaller stones may be used for wedging.</i>					
		If the wall is not founded on rock has it been bedded in a trench at least 300mm deep?					

Clause	Title	Check	Y/N	Response if N (default is "issue
				instruction")
11.2.1	General (continued)	Is the stone being roughly dressed and placed in courses with vertical joints staggered?		
11.2.2	Cement Grouted Rock walling	Note: minimum dimension may be reduced to 200mm for cement grouted walls, and smaller packing stones can still be used		
		Is each layer of stone being firmly embedded in cement mortar with a gap of 25mm between stone faces? Note: Mortar is 2 parts sand to one part cement and just sufficient water to be of workable consistency		
		Are weep holes being included?		
11.2.4	Feathering	Have grouted walls been finished on top with a 25mm layer of mortar bevelled at a slope of 3:1 to drain water to the front face?		

Notes	
Name	
Signature	
Date	

Form 11C Page 1 of 1

Project Na	me		
Chainages	From	То	

GROUP 11 – MASONARY FOR STRUCTURES								
CHECK	CHECK SHEET 11C – Laboratory or Field Tests Required							
clause	Title	Check						
		NOT RELEVANT						

Form 11D Page 1 of 1

GROUP	11 – MASONA	RY FOR STRUCTURES						
	CHECK SHEE	CHECK SHEET 11D – Measurement Records						
Clause	Title	Check	Unit	Y/N				
11.2.5	Measurement	All in rate for each category.	M ³					
	and Payment	Volume is to be based on dimensions shown on						
	-	drawings						
		There may be a need to make a joint measure of						
		lengths on Site but cross sections should be						
		taken as the nominal dimensions from drawings,						
		schedules, or written instruction.						
		Note: Stone pitched drains described in Group 9						
		are measured in linear metres. There appears to						
		be some inconsistency						

Notes	
Nomo	
Name	
Signature	
-	
Date	

GROUP 12 – PILING FOR STRUCTURES						
CHECK SH	IEET 12A -	Checks Required before physical works c	omme	ence		
Clause	Title	Check	Y/N	Response if N Default is " issue instruction")		
12.1	Descript- ion	Steel H Piles				
		Has the Contractor demonstrated that steel H Piles conform to AS 3679.1? Note: the Specification refers to AS 3678 and AS 3679.2 which appears to be incorrect as these standards apply to welded I beams, not to hot rolled universal sections. Contractor should produce a manufacturer's test certificate. Steel sections should also contain marks showing AS 3679; manufacturers mark, grade of steel and a reference to link to the test certificate. In addition to the yield strength there are additional identifiers for impact properties				
		including S for Seismic impact properties. Check drawings to see what is required.				
		Tubular steel pipe piles				
		Has the Contractor Demonstrated that steel plate confirms to AS 3678 (Grade 300 or 350), AS 1548 or AS 1594 HU24? <i>Note: HU24 may be a wrong designation</i> <i>in the Specification and HU300 may be</i> <i>what is required.</i> Are fabrication welds full penetration butt				
		welds with longitudinal joints staggered?				
		Reinforced Concrete Piles Have RC precast piles been made in conformance with Group 16 of the Specification?				
12.3	Driven Piles					
12.3.4.1	General	Has the Contractor submitted details of the equipment he proposes to use prior to commencing work?				
12.3.4.11 and 12.6.1	Ultimate Geotech. Strength	Has the Contractor supplied full details of his proposed method/s of assessment of pile ultimate geotechnical strength together with supporting details and calculations at least two week before piling is to commence?				

Clause	Title	Check	Y/N	Response if N Default is " issue instruction")
12.4	Bored Piles			
12.4.1	General	Has the Contractor provided details of the boring equipment he intends to use prior to commencing work?		
12.7.5	Sand Filling	When sand filling of bored piles is required, has the Contractor submitted a sample of the proposed sand fill prior to commencing filling? <i>Note: Required properties of the sand are</i> <i>not provided in the Specification</i>		
12.9.2	Design of Coffer Dams	Has the Contractor supplied details and drawings of the cofferdam and supporting calculations for the Construction Supervisor's review at least four weeks before he proposes to commence work on a cofferdam?		

Notes	
Name	
Signature	
Date	

GROUP 1	2 – PILING FO	DR STRUCTURES		
CHECK S	HEET 12B - (Checks Require During or After Physical Wo	orks	
		In sequence of activities		
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
12.1	Description	If Steel H piles are to be used, have they been approved? Note: For additional site check Steel sections should contain marks showing AS; manufacturers mark; grade of steel; and a reference link to the test certificate.		
		If tubular steel piles are to be used, have the piles been approved?		
		Do steel piles have suitable reinforced toes or shoes for driving? <i>Note: Unless shown otherwise on drawings</i> <i>pile toes should be cut off square to the</i> <i>longitudinal axis and not protrude.</i>		
		If protective coatings are required for steel piles, have these been applied in conformance with clause 18.9.4 and 18.10 of the Specification?		
		the piles been approved?		
12.3	Driven Piles			
12.3.2	Handling	Have RC piles reached an age of 28 days since casting?		
		Are suitable arrangements for lifting and stacking in place?		
12.3.3	Preparation for driving	Do RC piles have a driving shoe as shown on drawings?		
		Have piles been pitched at the correct rake?		
		Is a suitable pile helmet in place with adequate cushioning between the helmet and the pile?		
12.3.6	Pile Driving Records	Prior to driving have the pile number and overall length been marked on it near the head by stamping into the metal or other suitable means?		
		Has each pile been marked legibly by painting at intervals of five hundred (500) millimetres with marks to indicate the distance from the pile toe?		
12.3.4	Method of Driving			
12.1	General	Has the Contractor mobilised adequate pile driving equipment?		

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
12.1	General (continued)	Has the Contractor provided adequate notice of the intention to commence driving? Note: it is a Hold Point and the Contractor is not allowed to drive piles without the Construction Supervisor being present.		
12.3.4.2 and 12.3.4.3	Hammers	Are the size of the hammer and the drop within the requirements specified? Note: <u>Steel Piles</u> Drop hammer not less than 1.5 tons and not more than the combined weight of driving head and pile. Fall not more than 3m. For a diesel hammer not less than 40 kilo joules per blow. <u>RC Piles</u> , Drop hammer not less than 80% mass of the pile and in any case not less than 2 tons. Drop not more than 2m. Diesel hammers not less than 18 kJ per cubic meter of concrete with a minimum of 20kJ per blow. Set not to exceed 60mm, 50mm or 40mm for piles of 15m, 18m and > 18m respectively		
12.3.4.8	Water Jetting	Note: Water jetting is not allowed with Steel H piles.		
12.3.4.9	Pre-bored holes	Does the Contractor have prior written permission from the Contract Supervisor to use pre-bored holes?		Not allowed without written permission
12.3.5	Penetration	Has the Contractor driven the pile to the Maximum Toe Level or to a lower level to reach the required ultimate geotechnical strength?		
12.2	Accuracy	Are piles driven to within 1 in 100 from the vertical or the specified slope (rake) with no more than ±75mm out of place tolerance at the pile head?		Contractor to remove and re-drive or submit alternative proposals.
12.6	Pile Driving Records	Has the Contractor kept records giving details of the driving and penetration from commencement until completion for all piles driven, using the Employer's standard form for this purpose?		
		Has the Contractor submitted the required As Built information?		
12.3.7	Pile Heads	Have pile heads been cut off and treated as specified? Note: Steel Piles to have steelwork details carried out as shown on drawings. RC piles to have reinforcing pars extending a length of 40 diameters above cut off level		

Project Na	ne	
Chainages	FromTo	

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
12.4	Bored Piles			
12.4.2	Equipment	Does the Contractor keep available on site sufficient suitable casing to place in and protect a bore should an unstable stratum be encountered?		
12.4.3	Boring Logs	Is the Contractor keeping logs of the boring operations?		
		Is the Contractor carrying out SPT tests and taking undisturbed samples at 3m intervals? Note: The specification makes the Contract Supervisor responsible for transport and testing of the undisturbed samples		
12.4.4	Prevention of ingress	Is the Contractor taking precautions necessary to prevent the ingress of surface water or foreign matter into the completed boreholes and keeping them covered?		
12.7	Filling of Piles			
12.7.3	Reinforce- ment	Has reinforcement been supplied and installed in accordance with the drawings and requirements of Group 15 of the Specification?		
		Is it fixed into place so as to maintain in its correct position during concreting of the pile?		
12.7.2	Concrete Filling	Has the Contractor obtained permission to commence the concreting?		
		Has any water in the borehole been removed or a suitable method for pouring under water been agreed?		
		Does the concrete meet the relevant requirements of Group 16 of the specification and does it have a suitable slump?		
		Is the concrete being placed in an acceptable manner and in one continuous operation?		
		Where appropriate has the top of the concrete filling to the pile been brought above the required finished level to ensure pile head quality and bonding?		
12.7.4	Withdrawal of casings	When casings are to be withdrawn as concreting proceeds is a sufficient head of concrete being maintained above the toe of the casing?		
12.7.5	Sand filling	Is the moisture content approved and is the sand being placed and compacted, in layers not exceeding 300 mm?		
1	1		1	1

Project Na	me	
Chainages	FromTo	

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
12.9	Coffer Dams and Caissons			This is a Hold Point
12.9.2	Design	Have the design and drawings for the coffer dam been approved in prior to work commencing?		
12.9.3	Removal	Have all materials and temporary islands been removed and suitably disposed of?		
12.9.4	Caissons	Have caissons been positioned accurately to line and level?		

Notes	
Name	
Signature	
Date	

GROUP 12 – PILING FOR STRUCTURES			
CHECK	K SHEET 12C -	- Laboratory or Field Tests Required	
clause	Title	Check	Satisfactory Test results provided?
12.1	Description	Reinforced Concrete piles to be manufactured in conformance with Group 15 and 16 of the Specification.	
		Checks need to be made on quality control during manufacture, whether on or off the Site.	
12.4.3	Bored Piles	SPT testing at 3m intervals by Contractor Note: AS 1289.6.3.1	
		Undisturbed samples to be taken at 3m intervals by Contractor for transport and testing by Contract Supervisor Note: No tests specified and consultation with the designer may be required. Soil classification tests would be the minimum (particle size distribution, liquid and plastic limits) but shear strength testing may also be required	
12.6.2	Static Load Testing	Test Method is set out in the Specification	
12.7.2	Concrete filling	Slump tests and concrete cylinder tests will be required	
12.7.5	Sand Filling	Requirements not specified but should be a clean, well graded sand with suggested particle size limits 80% passing the 2.36 mm sieve and not more than 10% passing the .075 mm sieve.	

Notes	
Name	
Signature	
Date	

Form 12D Page 1 of 1

Project Na	ne	
Chainages	FromTo	••

GROUP 12 – PILING FOR STRUCTURES					
	CHECK SHEET 12D – Measurement Records				
Clause	Title	Check	Unit	Y/N	
12.3.6	Pile Driving	May need to be jointly agreed during driving or			
	Records	kept independently by Supervisor			
12.3.5	Penetration	Final toe levels of piles should be agreed as joint			
		records			
12.10.5	Splicing of	If separate provision is made in the Bill of			
	Piles	Quantities for splicing of piles, the number of			
		splices may need agreeing, but note that limits			
		are placed on splices to be measured for			
		payment by this clause.			
12.10.7	Re-purchase	If surplus steel piles are to be re-purchased an			
	of Steel	agreed measurement record should be made of			
	Piling	the quantity			
12.10.9	Filling to	Method of measurement to be proposed by			
	Piles	Contractor. Records will be required unless the			
		measurement is based on the internal volume of			
		the pile casing.			
18.11.2	Piles	Joint records may be required for the area	M2		
	(Protective	covered			
	Coating)			1	

Notes	
Name	
Signature	
Date	

GROUP 13 - FALSEWORK					
CHECK SH	CHECK SHEET 13A - Checks Required before physical works commence				
Clause	Title	Check	Y/N	Response if N Default is " issue instruction")	
13.1	General	Has the Contractor supplied detailed drawings and supporting calculations for review at least four weeks before he proposes to commence work on the Temporary Works?			
		Does the proposed falsework conform to the requirements of AS 3610?			

Notes	
Name	
Signature	
Date	

Project Name	
Chainages FromTo	•

GROUP 13 - FALSEWORK						
CHECK S	CHECK SHEET 13B - Checks Require During or After Physical Works					
Clause	Title	Check	Y/N	Response if N (default is " issue instruction")		
13.1	General	Has the Construction Supervisor provided written consent for the proposed falsework?				
		Is the falsework being erected in accordance with the approved design and drawings?				
		Is the falsework on a suitable foundation?				
		Has the release of falsework support to the permanent works been agreed?				
		Has all temporary works material been removed and the site made good to the satisfaction of the Construction Supervisor?				

Nataa	
INOTES	
Name	
Signature	
Date	

Project Na	me	
Chainages	From	То

GROUP 13 - FALSEWORK				
CHECK SHEET 13C – Laboratory or Field Tests Required				
clause	Title	Check		
		NOT RELEVANT		

Form 13D Page 1 of 1

Project Name
Chainages FromTo

GROUP 13 - FALSEWORK				
	CHECK SHEET 13D – Measurement Records			
Clause	Title	Check	Unit	Y/N
		Contractor responsibility to cover costs of		
		temporary works in other rates		
		Photographic Records would be useful		

Notes	
Nama	
Name	
Signature	
Date	

GROUP 14 - FORMWORK				
CHECK SHEET 14A - Checks Required before physical works commence				
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
14.1	General	Has the Contractor submitted the necessary documentation required by AS 3610? Note: See AS 3610 for full details but Contractor needs to supply plans, details, design assumptions, calculations, and method statement amongst other things		
14.2	Construct- ion	If steel forms are proposed, has the Contractor submitted designs for review prior to work commencing?		
14.5	Measure- ment and Payment	Note: The General Specification provides alternatives and it is suggested that matters be clarified before any work commences		
		commences		

Notes	
Name	
Signature	
Date	
Project Na	ne
------------	--------
Chainages	FromTo

GROUP 14 - FORMWORK					
CHECK S	CHECK SHEET 14B - Checks Require During or After Physical Works				
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")	
14.1	General	Has the Construction Supervisor been afforded the opportunity to adequately check the formwork prior to depositing concrete?		This is a Hold Point	
14.2	Construct- ion	Is the formwork free of defects and warping, and thoroughly cleaned?			
		Is the formwork timber suitable for the required class of finish?			
		Are the forms built true to line and braced in a substantial and unyielding manner to maintain position and shape?			
		Is the formwork free of gaps that would allow concrete laitance to leak out?			
		If external vibration is to be used, have suitable rubber paddings been provided between the formwork and any supporting surfaces?			
		Is the type of internal ties acceptable?			
		Are corners suitably bevelled or chamfered?			
		Have the locations of all inserts and hole formers been checked?			
		Has an acceptable release agent been applied to the formwork?			
16.9.7	Construct- ion joints	Are construction joints included as shown on drawings?			
14.2.4	Removal of Formwork	Has the Construction Supervisor been informed about the removal of formwork?			

Notes	
Name	
Signature	
Date	

GROUP 14 - FORMWORK				
CHECK SHEET 14C – Laboratory or Field Tests Required				
clause	Title	Check		
		NOT RELEVANT		

GROUP 14 - FORMWORK						
	CHECK SHEET 14D – Measurement Records					
Clause	Title	Check	Unit	Y/N		
14.5	Measurement	Alternatives are provided in the Specification but				
	and Payment	Quantities should clarify what is required				
		In Group 16 the measure and payment item for				
		concrete states that the cost of formwork is to be				
		considered as included in the rate for concrete.				
		Measurement records should be made of				
		formwork for hole formers				
		Note: The Specification is silent on the treatment				
		of hole formers and other box outs. Small box				
		outs are usually deemed to be included in the				
		rate. It would be beneficial if this was clarified in a				
		Supplementary Specification but if that is not the				
		case the details of all hole formers should be				
		measured as the Contractor is entitled to				
		payment				

Notes	
Name	
Signature	
eignature	
Date	

GROUP 15	5 STEEL REI	NFORCEMENT		
CHECK SH	HEET 15A -	Checks Required before physical works c	omme	ence
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
15.2	Materials	Has the Contractor provided an acceptable Manufacturer's test certificate for the reinforcement proposed for use three weeks prior to planned commencement of steel fixing?		
		If the Contractor has not provided an acceptable test certificate, has the Contractor provided the appropriate number of test pieces at least 3 weeks prior to planned commencement of steel fixing?		
		Note: one test piece for each 5 tonnes of steel reinforcement to be used with a minimum of 2 test pieces from each bar size		
		If the Contractor wishes to substitute an equivalent fabric to replace placed bars shown on drawings, has he submitted a detailed proposal with satisfactory supporting evidence?		
15.4	Cutting and Bending	Has the Contractor submitted a Reinforcement Bending Schedule showing bar mark, shape code (AS 1100.501), bent lengths, cut length and weights at least three weeks prior to the commencement of cutting and bending of reinforcement?		

GROUP 15 STEEL REINFORCEMENT					
CHECK S	CHECK SHEET 15B - Checks Require During or After Physical Works				
Clause	Title	Check		Y/N	Response if N (default is "issue instruction")
15.3	Protection	Is the steel reinforcem above the ground?	ent stacked in racks		,
		Has the surface of the detrimental rust, loose	steel been cleaned of scale, dust and oil?		
15.4	Cutting and Bending	Has steel been bent to dimensions shown on schedules? Note: Default for radii of diameter for Grade R2 diameter for grade D50	o the shapes and drawings and of bends is 2 x bar 50N and 3 x bar 00N.		
15.5	Placing and Fixing	Have all bars adjacent concrete element beer and is that cover main blocks or other devices	to a surface of the n checked for cover tained by concrete s?		
		Is all reinforcement firr	nly fixed with wire?		
		Is top steel in slabs firr spacer chairs?	mly supported by		
15.6	Splicing	Are spliced joints only the drawings, staggere overlap length? Note: if lap length requ shown on drawings the different situations are Specification	used were shown on ed and of adequate uirements are not e minimum lengths for described in the		
15.5	Placing and Fixing	Have all fixed bars been the drawings for size, of number and spacing a approved? Note: Tolerances are as Specification clause 10 Variation in cover Variation in position Starter bars Slabs and walls Bent bars Stirrups and ties Other bars	en checked against grade, shape, length, nd the fixing specified in 6. 15.2 6 mm 6 mm 15 mm or 10% of the indicated spacing, whichever is greater 6mm 12 mm	-	This is a Hold Point
15.6	Splicing	Note: If welding of rein	forcement is		
	(using welding)	17.3.4.11 will also ann	lv as set out below		
15.6		Do welding electrodes or AS 4857?	comply with AS 4855		
17.3.4 .11	Welding Reinforcing Steel	Are the welders adequ	ately qualified?		

Project Na	me
Chainages	FromTo

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
17.3.4 .11	(Continued)	Has a Welding Inspector been appointed?		
		Has the prior approval of the Construction Supervisor been obtained for butt welded splicing?		
		Does the welding procedure comply with AS 1554.3 or the bar manufacturer's recommendations? <i>Note: Welding of cold worked deformed</i> <i>bars is not allowed</i>		
		Has the Welding Inspector approved the welding procedure?		
		Has the welding procedure been tested in accordance with AS 1554.3 Clause 7 before it is used?		
		Do consumables comply with AS 1554.1? Note: Tack welds may use consumables that comply with 1554.3		
		Has the preparation of the fusion face been carried out in accordance with the approved procedure?		
		Are the welds being adequately inspected? Note: Location Tack welding requires welders to demonstrate qualification in presence of a Welding Supervisor and to be audited at six monthly intervals, with 'regular' inspections of welds for conformity with AS 1554.3. Fusion butt welds need to be 100% inspected by visual scanning with permissible levels of imperfection in accordance with AS 1554.3 Table 9.2		

Notes	
Name	
Signature	
Date	

Project Na	me
Chainages	FromTo

GROU	GROUP 15 STEEL REINFORCEMENT				
CHECK	SHEET 15C -	Laboratory or Field Tests Required			
clause	Title	Check	Response		
15.2	Materials	If a manufacturer's test certificate is not provided then tests will be needed as described in Appendix C of AS 4671			

Notes	
Name	
Signature	
Date	

Form 15D Page 1 of 1

Project Na	me	 	
Chainages	From	 То	

GROUP	15 STEEL REI	NFORCEMENT		
	CHECK SHEE	T 15D – Measurement Records		
Clause	Title	Check	Unit	Y/N
15.9	Measurement and Payment	Reinforcing bars measured in tons with spliced joints shown on drawings included in the measured quantity. Additional spliced joints agreed for the benefit of the Contractor are not measured. <i>Note: Bending schedules should provide a</i> <i>reliable means of measure</i>	ton	
		Mesh is measured in square meters placed but the measured quantity is to exclude the laps	M ²	

Notes	
Name	
Signature	
Date	

GROUP 16 – CONCRETE FOR STRUCTURES				
CHECK SH	EET 16A - Ch	necks Required before physical works com	mence	•
Clause	Title	Check	Y/N	Response if N Default is "issue instruction"
16.5	Materials			
16.4	Inspection	Has the Contractor provided 48 hours' notice of his intention to pour concrete?		
16.5.6	Testing	Has the Contractor provided 50kg of course aggregate and 25kg of fine aggregate for testing by the Construction Supervisor? Note: Notice period for the delivery of aggregates not provided but samples have to be tested for conformance with AS 2758.1 before they can be used which will take several days		It is a Hold Point that aggregates shall be approved in writing prior to being used.
16.6	Concrete Proportions and Design			
16.6.2	Grouts	Has the Contractor provided details of the proposed mix design (for grout) and 6 standard test specimens?		
16.6.3	General	Has the Contractor provided details of the concrete mix he proposes to use for each particular Grade of concrete for prior approval? Note: refer to Specification clause 16.6.3 for details required.		
16.6.4	Preliminary Mixes	Has the Contractor made preliminary mixes of Grades 40, 30, 25, 20 and 15 concrete, using the approved materials, under closely controlled laboratory conditions in the presence of the Construction Supervisor?		
		Has the Contractor made nine cylinders from each preliminary mix and tested them as described? <i>Note: 3 tested at 7 days and 6 tested at 28 days.</i>		
		Have the preliminary mixes been approved?		
16.8.2	Ready Mixed Concrete	Has the Contractor obtained prior approval for any intended supplier of Ready Mixed Concrete?		

Form 16A Page 1 of 2	2	Project NameToTo	
16.9.1	Program	Has the Contractor submitted a program detailing the sequence and timing of all concrete pours and curing periods for a structure, 7days prior to planned commencement?	

Notes	
Name	
Signature	
Date	

GROUP 16 – CONCRETE FOR STRUCTURES				
CHECK S	HEET 16B - (Checks Require During or After Physical Wo	orks	T
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
16.4	Inspection	Has the underlying ground condition been approved (under Group 4 of the Specification) prior to placing any blinding concrete?		
16.5	Materials			
16.5.2	Cement	Is the cement Ordinary Portland Cement Type GP (General Purpose) that complies with AS 3972? Note: Manufacturer's certificate may be required unless brand is well known		
		Has the Contractor obtained written permission if he intends to use cement other than Ordinary Portland Cement Type GP <i>Note: Other types of cement not allowed</i> <i>without written permission</i>		
16.5.7	Storage	Is cement being stored above ground level in weatherproof sheds?		
		Can any lumps of cement that are present be broken by applying only finger pressure?		Cement not to be used
16.5.3	Water	Is the water for the concrete clean and free of salts?		Test method?
16.5.4	Fine Aggregate	Has the sand been tested and approved?		
		If the source of sand is beach sand has it been stockpiled and thoroughly washed prior to use?		
16.5.5	Course Aggregates	Has the course aggregate been tested and approved?		
		Is the size of the course aggregate size compatible with the use of the concrete? <i>Note: 40mm for mass concrete, 20mm for</i> <i>reinforced concrete and 10mm for plinths</i>		
16.5.7	Storage	Are aggregates stored on well drained concrete slabs?		
15.5.8	Admixtures	Have admixtures in concrete been given prior approval?		
16.6.4	Preliminary Mixes	Have the preliminary mixes been approved?		
16.7	Control of Concrete Quality			
16.7.1	General	Is the Contractor sampling the concrete and preparing an adequate number of test cylinders as required?		

Clause	Title	Check		Y/N	Response if N (default is "issue instruction")
16.7.2	Sampling and Testing	Is the Contractor sa accordance with ap 1012? Note: It is consider are 1012.1 Sampling o 1012.3.1 Slump Te 1012.8.1 Compress test specimens 1012.9 Compression one sample of 2 cy concrete for testing minimum of 2 samp casting day) For initial use of tria cylinder a day for the tested at 7 days.	ampling and testing in opropriate parts of AS ed that the relevant parts of Concrete est sion and Indirect tensile we Strength Tests dinders per 15m3 g at 28 days (but with a ples of 2 cylinders per al mix, one additional he first 6 days to be		
16.8	Batching and Mixing				
16.8.1	On Site	Is site batched concrete being prepared by weigh batching and mixed using an approved type of mixer rotating at the correct speed?			
		materials have bee	n added 2 minutes?		
		charging the mixer Note: if temperatur time for placing to	e is more than 32 °C then be reduced to 30 minutes		
		Is weighing equipm concrete in accorda requirements of AS Note: The main red a calibration certific old	nent used for batching ance with the 3 1379? quirement is the need for cate less than 6 months		
16.8.2	Ready Mixed Concrete	Has the concrete te checked and the co for pouring? Note: Concrete temperature at time of placing $<32^{\circ}C$ $32^{\circ}C - 35^{\circ}C$ $>35^{\circ}C$	emperature been oncrete found acceptable Maximum elapsed time from charging of mixer 60 minutes 45 minutes Not Acceptable		No concrete to be used if temperature >35 °C (unless retarder has been added in which case discretion is allowed)

Project Name
Chainages FromTo

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
16.9	Placing and Compacting			
16.9.2	Placing	Have formwork and reinforcement been checked and approved prior to placing concrete?		This is a Hold Point
		Are chutes made of metal or metal lined and clean?		
		Is concrete being placed in a continuous manner?		
		Is the maximum concrete drop less than 2 m?		Vertical pipe to be used
16.9.3	Placing Concrete under water	Has prior approval been obtained for placing concrete under water?		
		Has the mix been adjusted to increase the cement content by 25%?		
		Is a tremie being used in such a manner that the concrete does not come into contact with water?		
16.9.5	Compaction of Concrete	Is there one vibrator of an approved type for every 5m ³ of concrete to be poured but with a minimum of 2?		
		Is at least one vibrator available as a reserve?		
		Are vibrators being inserted not more than 500mm apart?		
		Are vibrators being inserted so as to penetrate previously placed layers and vibration continued until air bubble cease to appear?		
		Are vibrators withdrawn slowly with an insertion period of at least 7 seconds but without over vibration causing segregation?		
16.9.6	Concrete for Bridge Decks	Is concrete in bridge decks being poured in approximately 2m wide strips transverse to the girders?		
40.44.0	Finishin	I have been dealer being finiskend bei bered		
16.11.3	Finishing Bridge decks	Have bridge decks been finished by hand screeding and power floating to the correct levels?		
		Has the deck been finished by brooming transversely to a rough surface?		
16.11.4	Curing	Are slabs being cured for 14 days and other elements for 7 days? Note: Adequate procedures for curing are an essential part of good concrete. The intention is to keep the concrete fully saturated during the curing period.		

Project Na	ne	
Chainages	FromTo	

Clause	Title	Check		Y/N	Response if N (default is "issue instruction")
		Has a membrane curi conforming to AS 379 use?	ng compound 9 been approved for		
16.12	Bituminous Paint to Concrete Surfaces	If bituminous paint is r surfaces (e.g. earth re type of paint been app applied in accordance manufacturer's recom	required to concrete etaining walls) has the proved and is it being with the mendations?		
16.13	No Fines Concrete	If no fines concrete is drawings is it being co to the information on t the requirements of cl specification?	shown on the onstructed according he drawings and/or ause 16.13 of the		
16.14	Tolerances	Do the final surfaces of comply with the specific Note:	of concrete structures fied tolerances?		
		Variations from vertical plumb	6mm in 3m plus 2mm, with a maximum limit of 20mm		
		Variations in location of sleeves and block outs Variations in X-section dimensions of columns and beam	Minus 6mm Plus 12mm		
		Footings Variation of dimensions on plan Misplacement of eccentricity Reduction in thickness	Minus 12mm 2% of width with a maximum of 50mm 5% of specified thickness		

Notes	
Name	
Signature	
Date	

GROUP 16 – CONCRETE FOR STRUCTURES						
CHECK	CHECK SHEET 16C – Laboratory or Field Tests Required					
clause	Title	Check		Satisfactory Test results provided?		
16.5.2	Portland Cement	If an acceptable manufacturer's certificate is not produced then test results from the Contractor (or independent testing by the Construction Supervisor) may be required to demonstrate compliance with AS 3972				
16.5.6	Testing	Contractor to supply the Construction Supervisor with 50kg course aggregate and 25 kg fine aggregate				
16.5.4	Fine Aggregate	To be tested for conformance with AS 2758.1				
16.5.5	Course Aggregates	To be tested for conformance with AS 2758.1				
16.6.2	Grouts	Contractor to provide 6 standard test specimens of the proposed mix for testing to AS 3700 (Masonary Structures) Note: As AS 3700 does not deal with testing it is considered that the reference should be to AS 3600, which in turn refers to AS 1012.9 for cylinder testing				
16.6.4	Preliminary Mixes	Contractor to make preliminary mixes of Grades 40, 30, 25, 20 and 15 concrete, using the approved materials, under closely controlled laboratory conditions in the presence of the Construction Supervisor				
16.7	Control of Concrete quality	Criteria for sampling and testing and acceptance are set out in this section of the Specification. 1012.1 Sampling of Concrete 1012.3.1 Slump Test 1012.8.1 Compression and Indirect tensile test specimens 1012.9 Compressive Strength Tests				

Notes	
Name	
Signature	
Date	

Form 16D Page 1 of 1

Project Name	
Chainages FromTo	

GROUP 16 – CONCRETE FOR STRUCTURES							
	CHECK SHEE	CHECK SHEET 16D – Measurement Records					
Clause	Title	Check	Unit	Y/N			
16.16	Measurement and Payment	Calculated from dimensions on drawings. Site records only required for any additional work instructed that is not shown on drawings	M3				
		Bituminous paint to surfaces is measured separately and may need agreed records as it will be covered up by backfill	M2				

Notoo	
Notes	
Name	
Signature	
Date	

GROUP 17 – STRUCTURAL STEELWORK					
CHECK SH	<u>IEET 17A - Cr</u>	necks Required before physical works c	omme	nce	
Clause	Title	Check	Y/N	Response if N Default is " issue instruction")	
17.1.3	Notice of Intention to Commence Work	Has the Contractor advised where the steelwork will be fabricated at least 6 weeks prior to the planned commencement of fabrication? Note: The Specification does not stipulate the time in which the Construction Supervisor has to respond but given the requirement of 17.1.4 and 17.1.1 below a maximum period of 14 days would appear necessary			
17.1.4	Sub- Contractors	Has the Construction Supervisor given written approval for any proposed sub- contractor for the fabrication work?		This is a Hold Point	
17.1.3	Notice of Intention to Commence Work	Has the date for commencement of fabrication been confirmed 7 days prior to commencement?			
17.1.1	Drawings, Procedures and Program	 Has the Contractor, at least 1 month prior to commencing any fabrication, submitted three copies of the relevant Workshop Drawings to the Construction Supervisor for review? Note: These Drawings shall clearly show all sizes, dimensions, markings and connections including loose packs, and shall set out the position sizes and length of all welds, nuts, bolts and washers as are necessary for the complete fabrication, assembly and erection of the steelwork. The Specification does not make this a Hold Point. The Specification does not give a time for a response but it is considered that this needs to be within a period of 14 days from receipt. Has the Contractor submitted for review, fourteen (14) days before the complete program of work, including details of procedures entailing weld sequences, distortion control, preheating Note: The Specification does not make this a Hold Point 			

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
17.2	Materials			
17.2.1	General	Has the Contractor provided a copy of the purchase order for materials prior to its issue to the Supplier?		
17.2.2	Standards of Materials			
17.2.2.1		If the Contractor intends to use material that is not certified as conforming to Australian Standards, has a report been submitted? Note: the Report should include a complete description of the material, including chemical composition, mechanical properties, etc. and the differences between the relevant Australian Standard and the proposed standard, highlighting any areas where the proposed standard has less stringent requirements. The Specification is silent on what happens next but it should be assumed that the Construction Supervisor has complete discretion on whether to accept alternative standards. Acceptance may need to be in the form of a Variation.		
17.2.5	Certificates	Has the Contractor submitted acceptable certificates showing that all the materials that have or will be brought to the Site conform to the Specified AS Standards, or some other Standards that have been approved in writing?		
17.3.4.7	Qualificat- ions of Personnel	Has the Contractor submitted details of the proposed Welding Inspector at least 10 days prior to the commencement of any fabrication involving welding procedures?		
17.3.5	Stud Connectors			
17.3.5.1	General	Has the Contractor submitted acceptable certification from proposed Suppliers showing that the materials for studs and bases comply with AS 1554.2?		This is a Hold Point under 17.3.5.1
17.3.5.3	Certification of Welders	Has the Contractor submitted certification to show that proposed welders are qualified to standards set out in AS 1544.2?		This is a hold point under 17.5.5.1

Clause	Title	Check	Y/N	Response if N Default is "issue instruction")
17.8.1	Erection Procedures	Has the Contractor submitted his detailed erection proposal to the Construction Supervisor for approval at least 14 days before erection is to commence? Note: Additional members and attachments used to facilitate erection may be approved by the Construction Supervisor if they are affixed in a manner which does not weaken permanent steelwork. Welded outstands and attachments to assist the erection will be permitted providing that in the opinion of the Construction Supervisor such attachments neither adversely affect the serviceability nor mar the final appearance of the structure.		
17.8.7.1	Supply (of HSFG Bolts)	Has the Contractor supplied certificates one month before proposed use to demonstrate that the proposed High Strength Friction Grip bolts comply with AS 1252?		

Notes	
Name	
Signature	
Date	

GROUP 1	GROUP 17 – STRUCTURAL STEELWORK			
CHECK S	HEET 17B - (Checks Require During or After Physical Wo	orks	
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
17.3	Fabrication	Note: The requirements for inspection in this section should be carried out by an Inspector who is familiar with steel fabrication procedures and who can visit the workshop where the fabrication is being carried out.		
17.3.2	Cutting	Has the cutting of steel been carried out in accordance with the approved procedures?		
17.3.3	Staighten- ing	Has the straightening of steel been carried out in accordance with the approved procedures?		
17.3.4	Welding			
17.3.4.2	Equipment	Is welding equipment conforming to AS 1554 or AS 60974.6?		
17.3.4.3	Consum- ables	Has the Contractor produced a certificate from the manufacturer that states that the batch of consumables being used conforms to AS 1554.1?		
17.3.4.4	Welding Procedures	Has an approved Welding Inspector been appointed?		
17.3.4.6	Qualificat- ion of Welding Procedures	Have the welding procedures been documented in a welding procedure qualification record and a welding procedure specification?		
		If the procedures are deemed to be pre- qualified in accordance with AS 1554 has the Welding Inspector certified the Welding Procedure Specification?		
		If the procedures require qualification by testing, has the Welding Inspector checked that all test pieces have been welded according to the Welding Procedure Specification?		
		After testing, has the Welding Inspector certified the procedures?		
17.3.4.6	Qualificat- ion of Welding Personnel	Has the Contractor demonstrated that all the welders, inspection technicians and welding supervisors have acceptable qualifications?		
17.3.4.5	Safety Require- ments	Is the Contractor carrying out the work using adequate safety measures?		
17.3.4.4	Welding Procedures	Has the Welding Inspector inspected all welding?		

Clause	Title	Check	Y/N	Response if N Default is "issue instruction"
17.3.4.9	Inspection of Welds	Are welds being inspected in accordance with methods nominated in AS 1554.1 and the requirements of clause 17.3.4.9 of the Specification?		
17.3.4 .11	Welding of Reinforcing Steel	Note: Requirements under this section have been covered in Group 15 of the manual		
17.3.5.1	Shear Connectors	Has material and welder certification been provided and accepted?		This is a Hold Point
17.3.5.4	Testing of Finished Stud Welds	Has every stud been tested by ring testing and, if necessary, bend testing as specified?		
		Have studs that failed the tests been satisfactorily repaired?		
17.3.6	Holes for bolts	Are all holes being formed by drilling, with any burrs and defects removed? Note: Punching is not allowed		
		Are reamed and fitted holes being prepared using templates and pilot drilling to 3mm less than final size?		
		Are final hole sizes 2mm larger than the bolt size? Note: The inner plies of a structural connection fastened by high-strength (friction grip) bolts may have a diameter not be more than 3 mm larger than the nominal diameter of the bolt.		
17.3.7	Marking	Are all parts carefully marked to facilitate final assembly?		
17.4	Trial Assembly	Have trial assemblies been carried out as required in the presence of the Construction Supervisor?		
17.5	Tolerances	Has all fabrication work been carried out to tolerances shown on the drawings or otherwise in accordance with AS 4100 Clause 14.4?		
17.7	Delivery to Site	Have all parts been inspected and passed prior to leaving the Contractor's workshop for delivery to Site?		This is a Hold Point
		Are all components adequately protected from damage during delivery?		
17.8	Erection			
17.8.1 and 17.8.2	Erection Procedures and Additional Members	Has the Contractor's proposed erection procedures been submitted and approved?		

Project Na	ne	
Chainages	FromTo	

Clause	Title	Check	Y/N	Response if N Default is "issue instruction"
17.8.3	Storage	Are all steelwork components stored clear of the ground and in a manner that allows checking?		
17.8.4	Straighten- ing	If straightening is required has the Contractor obtained prior approval?		
17.8.5	Contact Surfaces	Have contact faces been cleaned and prepared?		
17.8.6	Assembly	Have all components been assembled according to the drawings and following all match marks?		
		Have high tensile bolts been assembled with one hardened washer under the turned element (nut or bolt head), with the washer assembled with any convexity outwards?		
17.8.7.1	HSFG Bolts	Have the proposed bolts been approved?		
17.8.7.2	Assembly of Connection	Is the Contractor following the requirements of Specification 17.8.7.2, 17.8.3 and 17.8.4?		
17.8.8	Erection of Handrailing	Are handrails set to a tolerance of ±3 mm vertically and horizontally?		
17.8.10	Accuracy of Assembly	Has steelwork been erected to line, level and camber shown on the drawings?		
17.8.11	Misfits	If there are any misfits of hole alignments has the proposed method of rectification been given prior approval by the Construction Supervisor?		

Notes	
Name	
Signature	
Date	

Form 17C Page 1 of 1

Project Na	ne	
Chainages	FromTo	•

GROUF	GROUP 17 – STRUCTURAL STEELWORK			
CHECK	SHEET 17C -	Laboratory or Field Tests Required		
clause	Title	Check		
		No on site testing		

Form 17D Page 1 of 1

Project Na	me	
Chainages	FromTo	

GROUP	GROUP 17 – STRUCTURAL STEELWORK			
	CHECK SHEE	CHECK SHEET 17D – Measurement Records		
Clause	Title	Check	Unit	Y/N
17.9	Measurement and Payment	All in rate except for holding down bolts and bearings which may be measured separately	ton	

Form 18A Page 1 of 1

GROUP 18 – PROTECTION OF STEELWORK				
CHECK SH	IEET 18A - Ch	necks Required before physical works c	omme	ence
Clause	Title	Check	Y/N	Response if N Default is " issue instruction")
18.1.1	Surface Preparation	Has the Contractor provided satisfactory documentation to demonstrate that cleaning solvent complies with AS1627.1?		
18.9	Protective Systems for Steelwork	Has the Contractor provided the required information for all paint systems proposed for use, at least 20 working days prior to its proposed use?		
18.2	Galvanising	Has the Contractor provided satisfactory documentation to demonstrate that all galvanised fasteners that will be used conform to AS 1214?		

Notes	
Name	
Signature	
Date	

GROUP 18 – PROTECTION OF STEELWORK				
CHECK S	HEET 18B - C	Checks Require During or After Physical Wo	orks	1
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
18.1	Shop Painting			
18.1.1	Surface Preparation	Following the trial erection (Group 17.4), has the surface of all steelwork been adequately cleaned with approved solvent and prepared to Class 3 of AS 1672.4?		
18.1.2	Priming	Have all surfaces (except those specified as not to be primed) been given an approved Prime Coat? Note: Surfaces that are not to be primed are described in clause 18.1.3)		
18.2	Galvanising	Has the Contractor carried out any tests that are required to be carried out under AS 4680?		
18.3	Field Painting			
18.3.2	Painting	Is the paint system approved? Note: It should be the one that was submitted for prior approval under clause 18.9?		
		Is the paint being applied in accordance with the Manufacturer's instructions?		
18.4	Transport and Storage	Is the paint being stored in accordance with the Manufacturer's recommendations?		
		Is the paint less than 12 months old or within its recommended shelf life?		
18.6	Repairs to Damaged Surfaces	Have damaged areas of protective coating been cleaned back to base metal and the edges of the damaged area bevelled?		
		Has the touch up paint been applied to overlap existing paint by 50mm?		
18.8	Completed Joints	Have the unpainted but exposed parts of HSFG joints, including exposed parts of bolts, been painted as specified within 10 days of the joints being inspected and approved?		
18.9.3	Seismic Restraints	Have seismic restraints that are not to be covered in concrete been protected as specified in this clause of the Specification?		
Notes				
Signature		Date		

Form 18C Page 1 of 1

Project Na	me		
Chainages	From	To	

GROUF	GROUP 18 – PROTECTION OF STEELWORK					
CHECK	SHEET 18C -	Laboratory or Field Tests Required				
clause	Title	Check		Response		
18.9.2 (e)	Application	Coating thicknesses will need checking with paint gauges. Prime Coat to be 75 microns and top coats 100 microns				

Notes	
Name	
Signature	
Date	

Project Na	ne	
Chainages	FromTo	•

GROUP 18 – PROTECTION OF STEELWORK					
CHECK SHEET	18D – Measure	ement Records			
Clause	Title	Check	Unit	Y/N	
17.9	Measurement	Included in the rate for steelwork.			
	and Payment				

Form 19A Page 1 of 1

Project Name	
Chainages FromTo	•

GROUP 19	GROUP 19 – MISCELLANEOUS BRIDGEWORK ITEMS					
CHECK SH	CHECK SHEET 19A - Checks Required before physical works commence					
Clause	Title	Check	Y/N	Response if N Default is "issue instruction")		
19.2.2	Elastomeric Bearing	Has the Contractor submitted test certificates giving the physical properties and mechanical properties for each bearing proposed for use? <i>Note: All bearings shall be indelibly</i> <i>marked with appropriate bearing type</i> <i>number and a unique number for</i> <i>correlation to test certificates.</i> Does the elastomer conform to AS				
		5100.4 with hardness IRHD 60 ±5?				
19.3.4	Waterstop	Has a brand of waterstop been proposed for approval?				
19.3.5	Joint Filler	Has the brand and type of the jointing material been submitted for approval?				
		certificates detailing the compressive stress/strain relationship for the joint filler? Note: The stress to compress the joint filler to 50 percent of its original thickness shall be not less than 0.1 MPa and not greater than 0.3MPa.				
19.3.6	Joint Sealant	Has the brand of the joint sealant been submitted for approval?				
			1	1		

Notes	
Name	
Signature	
Date	

GROUP 19 – MISCELLANEOUS BRIDGEWORK ITEMS				
CHECK S	<u>HEET 19B - (</u>	Checks Require During or After Physical Wo	orks	
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
19.2.2	Elastomeric Bearings	Do the bearings have indelible markings showing the appropriate bearing type number and a unique number for correlation to test certificates? <i>Note: Ensure that bearings on site are those</i> <i>covered by submitted test certificates</i>		
		Are bearings being installed to the correct level following the procedure set out in the Specification?		Alternative procedures need prior approval
19.2.3	Other Bearings	Have bearings been installed in to correct line and level in conformance with the drawings?		
19.3.1	Impact angles	Are impact angles galvanised to AS 4680?		
		Has care been taken to ensure concrete is worked into the corners and air is expelled?		Suggested that placing concrete be witnessed
19.3.2	Pre-formed Neoprene Joints	Have compression joints been installed in one continuous length?		
19.3.4	Waterstops	Has the water-stop brand been approved?		
		Is the water-stop being installed and spliced in accordance with Manufacturer's recommendations?		
19.3.5	Joint Filler	Has the material for the joint filler been approved?		
		Is the joint filler being applied in accordance with the Manufacturer's recommendations?		
19.3.6	Joint Sealant	Has the sealant material been approved?		
		Have adjacent surfaces of the concrete been masked?		
		is the sealant being applied in accordance with the Manufacturer's recommendations?		
19.4	Scuppers	Are scuppers formed using UPVC pipes that comply with AS 1260?		
		Are they being arranged so that the exposed concrete surfaces will not be stained?		
19.5	Epoxy Mortar	Is the material of an approved type?		
		Is it being used in accordance with the Manufacturer's recommendations?		

Clause	Title	Check		Y/N	Response if N (default is "issue instruction")
		Does the sand comply Specification? Note: Oven dried, har material free of all org	/ with the d, sharp, siliceous anic material.		
		AS 1152 Sieve Size	Percentage Passing,		
			By Mass		
		1.18 mm	100		
		0.600 mm	10		
		0.300 mm	0.2		
		0.150 mm	0		
19.6	Epoxy Adhesive	Is the adhesive of an a	approved type?		
		Are the surfaces to be	threatened		
		roughened or etched a	and cleaned with		
		acetone prior to applic	cation?		
		Is the adhesive being with the Manufacturer	applied in accordance 's recommendations?		

Notes	
Name	
Signature	
Date	

Form 19C Page 1 of 1

Project Name
Chainages FromTo

GROUP 19 – MISCELLANEOUS BRIDGEWORK ITEMS				
CHECK	SHEET 19C -	Laboratory or Field Tests Required		
clause	Title	Check	Satisfactory Test results provided?	
19.2.2	Elastomeric Bearings	Strength of mortar under bearings will need to be tested and confirmed AS 1012.8.1 and AS 1012.9		
19.4	Epoxy Mortar	Sand may need testing for moisture content and grading.		

Notes	
Name	
Signature	
Date	

GROUP 19 – MISCELLANEOUS BRIDGEWORK ITEMS				
CHECK	CHECK SHEET19 D – Measurement Records			
Clause	Title	Check	Unit	Y/N
19.7	Measurement and Payment	Payment by number of each item		

GROUP 20	- RIVER TRA	INING AND BANK PROTECTION		
CHECK SH	IEET 20A - Cł	necks Required before physical works c	omme	ence
Clause	Title	Check	Y/N	Response if N Default is " issue instruction")
20.1	Gabions and Reno Mattresses	Has the Contractor demonstrated that the gabions and mattresses that have or will be delivered to the site meet the requirements of the Specification? Note: Wire to AS 2423 with tensile strength 350Mpa Wire to be galvanised to AS 4534 Class W10Z or W10Z5A 0.55mm thick PVC coating to wire to AS 2423 Appendix E Wire thickness (core) as follows: Gabion mesh 2.7mm Mattress mesh 2.0 mm Selfedge gabion 3.4 mm Selfedge mattress 2.7 mm Binding wire 2.0 mm Tolerance on wire $\pm 2.5\%$ Tolerance on dimensions Length $\pm 3\%$ Width ± 25 mm Other dimensions $\pm 3\%$		
20.1.9	Filling Material	Is the proposed filling material hard durable stone of minimum dimension 100mm and maximum 250mm?		
20.1.2	Bank Protection	Have any necessary instructions for the detailed site layout of protection works been issued?		
20.1.3	River Training	Have any necessary instructions for the detailed site layout of river training works been issued?		
20.6.1	Geotextile Properties	Has a suitable brand of geotextile been proposed that meets the specified requirements of this clause in the Specification?		
1	1		1	1

Notes	
Name	
Signature	
Date	

GROUP 20 – RIVER TRAINING AND BANK PROTECTION				
CHECK S	HEET 20B - (Checks Require During or After Physical We	orks	
Clause	Title	Check	Y/N	Response if N (default is "issue
20.1	Gabions	Have the brand of gabions and mattresses been approved?		
20.1.11	Fabrication	Are the gabions being unfolded and stretched before fabrication? Are the corners joined together with three		
		around the two selfedges through each mesh in turn?		
20 1 12	Placamont	Are corpore being stratched with crow bars?	-	
20.1.12	Filling	Are the baskets being cross tensioned at third points in the height of the gabion? Note This applies for baskets that are 1m in height.		
		Are baskets topped off with the smaller sized stone to a level 25mm to 50mm above the top with lids then stretched over with crow bars?		
20.2	Bank Protection	Have the banks been adequately trimmed and prepared before gabion or mattress construction work commences?		
20.3	River Training	Is the level of the top of the gabions or mattresses approximately 600mm above normal river level?		
20.6.2	Installation (of Geotextile)	Is the construction method suitable for avoiding tears and punctures to the geotextile?		
		Are laps being made with overlap of at least 300mm above water level and 900mm below water level?		
20.7	Rock Rip Rap	Does material proposed as rip rap consist of hard, durable stone without weak laminations or cleavages, and which is predominantly angular in shape?		
		Is stone of varying size ranging from 100mm to 800mm but with at least 50% within a range 150mm to 600mm?		
		Have the slopes to receive the rip rap been adequately prepared?		
		produce a minimum of voids?		

Form 20B Page 2 of 2

Project Na	me
Chainages	FromTo

Clause	Title	Check	Y/N	Response if N (default is "issue instruction")
20.8	Concrete Armouring	If concrete armouring is shown on the drawings has it been manufactured and placed as required?		

Notes	
Name	
Signature	
Date	
Form 20C Page 1 of 1

Project Na	me		
Chainages	From	То.	

GROUP 20 – RIVER TRAINING AND BANK PROTECTION									
CHECK	CHECK SHEET 20C – Laboratory or Field Tests Required								
clause	Title	Check							
		NOT RELEVANT							

GROUP 20 – RIVER TRAINING AND BANK PROTECTION												
CHECK SHEET	CHECK SHEET 20D – Measurement Records											
Clause	Title	Check	Unit	Y/N								
20.1.14	Measurement	Nominal volume placed	M ³									
	(gabions and											
	mattresses)											
20.6.3	Geotextile	Square metre shown or directed and no	M ²									
		allowance for laps										
20.9	Rip Rap	Cubic metre supplied and placed. This suggests that for irregularly sized stone a method of measuring at the point of supply will be required	M ³									

Notes	
Name	
Signature	
Date	

Project Na	me	
Chainages	From	.То

"PROJECT NAME"

D	AYWORKS RECC	ORD SHEET							
ACTIVITY									
Instruction Ref. No	ction Ref. No DATE OF WORK//								
CONTRACTOR'S REF NO	CONTRACTOR'S REF NO								
ΡΙ ΔΝΤ/Ι ΔΒΟΙ ΙΒ ΙΤΕΜ	HOURS								
	10010								
1.									
2.									
3.									
4.									
5.									
6.									
7.									
MATERIALS									
THE ABOVE DETAILS ARE AGRE	ED								
SIGNED (Construction Supervisor's Rep.)									
SIGNED (for Contractor)									
DATE//		DATE//							

Project Na	me			
Chainages	From	То	D	

APPENDIX A Forms for Contractor Notifications

Forms for Approval to Commence

3		VAN	UATU	INFR	₹AST	RUCTL	JRE REF	IABILI	FATION /	AND		
		IMPF	NOVEN	VENT	r PR(OJECT						
		COMF	ONENT	Г:								
Long God yurri yakete	5	APP	ROVA	L TC) C(OMMEN	CE - C	ONCR	ETE PO	UR		
To has	···hmitter											
			NINA		7						_	
REQUESI	TO POU	R		\vdash		-						
Location	Road	1				Elemen	t					
	Structure	,										
	Chainage						Concrete	e pour :	class		_	
Will be av	ailable for	inspection	n on	(date))	_			volume		m ³	
			<u> </u>	(time))				(date)		_	
	•••••			++		D((time)		_	
Contractor	Dy : r)			+-+		(E	naineer)	÷	· · · · · · · · · · · · · · · · · · ·			
)		Data	+		`	Time		Data			
	Time		Date	++					Date		_	
To be c	omplete	d by EN	IGINE	ER								
INSPECTC	DR:			\vdash		Time		Date				
				+							+	
	UNLIGT .		ITEM	+	A	APPROVED	R	EJECTED				
			Cleanli	22201								
			Ultan.									
			Joints	\vdash				<u> </u>				
			Formwo	ork								
			Reinfor	cemen	1t				Attach re	ar sched	ule	
			Cover	+-+								
			0010.	<u></u>								
			Inserts	& cut-	outs							
			Dimens	sions					Attack	akotoh		
			Line &	level						SKELON		
Rejection of	of any of the	e above iten	ns will re	esult in	ו rejec	tion of this	s request -	a new su	ubmission v	will then be	• required	
ENGINEEF	RS REQUI	IREMENTS	/ COM	MENTS	3 :							
				++								
				+-+		++				· · · · ·		
						+						
											_	
				++								
				+			REG	QUEST	- APPRO	VED / H	REJECTED	
				+					(Eligning	Jn as app	(opnate)	
sued or	n behalf	of the I	Engine	eer :		Rece	ived on	behal	f of the	Contra	ctor :	
Cianad				++			Cianad					
Signea				+			signea					
Time		Date		+-+			Time		Date			
		D 0.10				-						

Form ATC 2 Page 1 of 1

Project Name	
Chainages FromTo	

*		VA	NUA	TU	INFR	ASTR	UCTUR	RE RE	HAE	BILI			٩ND	
48		IMI	PROVI	ЕМЕ		ROJEC	т							
		COI	MPONE	NT:										
		AP	PROV	AL	то с	OMME	ENCE -	EART	HWC	ORK	S			
Long God wirth stanse	<u></u>													
To be sul	omitted	by CO	NTRA	стс	D R									
REQUEST 1	го сом	MENCE E	ARTHW	/ORK	S									
Location :	Road				Ор	eration :	CUT / F	ILL						
	From	(Ch)					(Highlight as	appropria	te)					
	То	(Ch)												
Will be avai	lable for	inspectior	non	(date (time	e) e)									
Requested t	by :					Re	eceived by	:						
(Contractor)						(E	ngineer)							
	Time		Date				Time			Date				
To be con	pleted	by ENG	INEER	l										
For ENGINE	ER :					Time		Date						
ITEM CHEC	KLIST :													
	ITEM					YES		NO						
	Posses	sion of Site	e grante	d										
	Crop co	unting com	nplete											
	Setting	out in plac	e											
	Survey	carried out	after cle	aring										
	Matoria			nittoc	1					roqui	od hofe		borrow	
	Ivialena			nillec							eu beiu	ie any	DOITOW	
prior to com	nt areas	to be insp g fill opera	ected a ations	itter	cleag a	Grub o	perations	: testing	g may	be re	quired]		
Should signif	icant dan	nage or de	ay be c	auseo	d, prior t	o or duri	ng construc	tion, a r	new su	ubmiss	ion will	be rea	quired	
Rejection of a	any of the	e above iter	ms will r	esult	in rejec	tion of th	is request -	a new s	submis	ssion	will ther	ı be re	quired	
During the co	ourse of c	onstruction	n adequa	ate pr	ovision	is to be a	allowed for t	the Engi	neer to	o unde	ertake t	esting	in	
accordance v	with Spec	ification												
ENGINEERS		REMENTS	/ COM		rs ·							_		
												_		
						REQUE	ST - AP	PROVE	D (In	Part	/ Full)/ R	FJECTE	-D
							(Hig	hlight as a	appropr	iate)	,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
						Approve	ed area :							
Issued on	behal	f of the	Engi	neer	:	Rece	eived on	beha	lf of	the	Cont	racto	r :	
Sianed							Signed							
Time		Date					Time		Da	ate				

Form ATC3 Page 1 of 1

Project Na	me	
Chainages	From	То

A .		ναν		FRAS									
C2		IMPE			ROJE	СТ							
		COME											
Long God yuni 42	NO TO THE OWNER	AP	PROVAL	то	CON	IMEN	CE - P	AVEN		& SEA	L WO	RKS	
To be s	ubmitted	l by CO	NTRACT	OR									
REQUEST	то сом	MENCE P	AVEMENT/	SEAL	WOR	۲S							
Location :	Road				Oper	ration :	Subarade	(for S-B	lase)				
	From (Ch)						Sub-base	(for Bas	se)				
	To (Ch)			_			Basecours	se (for F	Prime)				
Will be av	ailable for	inspection	non	_			19mm sea	l (for 9r	seal) nm sea	1)			
	(date)	mopoonon					9mm seal			,	(Tick as	appropriate)	
	(time)												
Requested	by :			_		F	Received b	y :					
(Contractor)					(Engineer)						
	Time		Date				Time			Date			
To be c	ompleted	d bv EN	GINEER										,
INSPECTO	R ·	j		_									
				_									
ITEM CHE	CKLIST :			_	APF	PROVED	RE	JECTED		Tim		D Date	
		Select sub	-grade mate	erial								Date	
		Visual Insp	pection										
		Tolerance	Control	_									
		Material R	equirements	2									
		(Results attack	hed)	,									
Should sig	nificant dan	nage or del	av be cause	ed pric	or to or	durina	constructio	n a ne	wsubm	uission w	ill be rea	uired	
Rejection of	f any of the	above iter	ns will resul	lt in rei	ection	of this r	request - a	new su	hmissio	n will th	en he reg	uired	
					conorr		cquest a		biiiissic				
ENGINEEF	RS REQUI	REMENTS	/ COMMEN	ITS :									
				_									
				_									
				_									
				_									
						REQU	EST - A	PPRO\	/ED(l	n Part /	/ Full)/	REJECTE	Ð
				_		A	()	Highligh	it as ap	propriate	e)		
				_		Approv	ed area :						
Issued o	n behal	f of the	Enginee	er:		Rec	eived o	n beł	half of	f the (Contrac	tor:	
Signed							Signed						
Time		Data					Time			Data			
TITLE		Dale					me			Dale			

APPENDIX B Site Record Forms

VANU	VANUATU INFRASTRUCTURE REHABILITATION AND IMPROVEMENT PROJECT															
Compone	nt													DATE		
DAILY REP	AILY REPORT SHEET - EARTHWORKS															
	Record No.	1	2	3	4	5	6	7	8	9	10	11	12	Comment	s	
ROAD																
SOURCE																
	Borrow @ Ch	T0 T				<u> </u>		L					<u> </u>			
MATERIAL		15 - 10ps			VR - Weath	erea rock	KK - KIP	реа госк	BR - Blas	Sted FOCK		litable mat	eriai T			
CUT METHO	C	DR - Drill	BL - Bla	st LT-L	oad/exc to	truck DF	- Doze to f	ill DL - D	oze to load	der/exc E	ST - Batter	trim				
MAJOR PLA	NT	BD(?) - Bi	ull d ozer (w	/ith referer	nce.no.) E	 X(?) - Exc	avator L	D(?) - Loa	der RD(1) - Rock (l Irill					
											1	T	1			
HAULAGE	No. 53															
	NO. 5M°															
	No. 8m ³															
MOVEMENT																
(Link using ar	rows)															
DEPOSITION	i															
	Fill @ Ch															
	Spoil @ Ch															
FILL LAYER		RF - Rock	fill SP	- Spoil	CF - Comm	non fill S	SF - Select	fill BT -	Batter trin	n SP-5	Stockpile					
							_									
		BD(?) - B	ull d ozer (w	ith referer	nce no.) E	X(?) - Exc	avator R	L(?) - Rol ∐ │	er GD - (Grader		1	т			
Quality Car	trol Manuel		5-31										ļ			
	nor manual	versio	n i June	2018												
				+												
			1					1		1		1				

VAN	IUATU INF	RASTR	UCTURE	REHAE	BILITATI	ON AND	IMPRO	VEMENT	PROJE	СТ	
COMPON	ENT:							DATE			
DAILY RE	PORT SHE	ET - DF		(Culvert	Installati	on)	IN	SPECTOR			
				(0001							
	Record No.	1	2	3	4	5	6	Abbreviatio	ons		
LOCATION	Road							Roads (allocate a	bbreviatio	on)
	Chainage							Indicate	as approp	riate	
	Portion							HW(Lor	R) - Half w	idth FW	- Full wid
DETAILS	Purpose							cc - cro culvert	SD - Sto	AC - Ac rm drain	DT -
	Туре							P - Pipe	B - B ox	A - A rc	:h
	No. Barrels							Indicate	as approp	riate	
	Size							Indicate	as approp	riate - size	in mm's
	Material							PC - Pre concrete metal (S	ecast conc CM(So Steel or Alu	rete IC - orA) - Corru iminium)	Insitu gated PVC
		p anels	BF - Ba	ckfill CI	H(I/O) - C	hute(Inlei	/Outlet)				
MAJOR PL/	ANT	CR(1/2) - Cra	ne BD((1/2…) - B	ull d ozer					
		EX(1/2) - Ex ca	avator	CT(No of	f) - C onci	rete				
LABOUR	Foreman/LH										
	Carpenter										
	Steel fixer										
	Labourer										
					1		1	I			

COMPONENT DATE DATE DALY REPORT SHEET - STRUCTURES NAME = B1 NAME = B2, ETC NSPECTOR NSPECTOR Record Ma 1 2 3 4 5 6 7 8 9 10 11 12 Comments Record Ma 1 2 3 4 5 6 7 8 9 10 11 12 Comments LOCATION Site 1 2 3 4 5 6 7 8 9 10 11 12 Comments LOCATION Site 1 2 3 4 5 6 7 8 9 10 11 12 Comments 1 <t< th=""><th>VAN</th><th colspan="11">VANUATU INFRASTRUCTURE REHABILITATION AND IMPROVEMENT PROJECT</th></t<>	VAN	VANUATU INFRASTRUCTURE REHABILITATION AND IMPROVEMENT PROJECT																
DALLY REPORT SHEET - STRUCTURES NAME = B1 NAME = B2, ETC INSPECTOR INSPECTOR SITE ROAD NAME = B1 NAME = B2, ETC Inspector Inspector ROAD 1 2 3 4 5 6 7 8 9 10 11 12 Comments ROAD 1 2 3 4 5 6 7 8 9 10 11 12 Comments ICCATION Site Inspector Inspector Inspector Inspector Inspector Inspector WORK ITEM(s) Inspector Inspector Inspector Inspector Inspector Inspector MAJOR PLANT Inspector Inspector Inspector Inspector Inspector Inspector Inspector IABOUR Inspector Inspector Inspector Inspector Inspector Inspector Inspector IABOUR Inspector Inspector Inspector Inspector Inspector Inspector Inspector IABOUR Inspector Inspector Inspe	СОМРО	NENT													DATE			
Bit ROAD NAME = B1 NAME = B2, ETC Record No. 1 2 3 4 5 6 7 8 9 10 11 12 Comments LOCATION Site			ст о'	TRUCTU	DES										ODEOTOD			
NAME = B1 NAME = B2, ETC Record No 1 2 3 4 5 6 7 8 9 10 11 12 Comments LOCATION Site 1 2 3 4 5 6 7 8 9 10 11 12 Comments LOCATION Site 1 2 3 4 5 6 7 8 9 10 11 12 Comments LIOCATION Site 1 2 3 4 5 6 7 8 9 10 11 12 Comments Element Income		FORT SHE	EI - 3	IRUCIU	RES										SPECIUR			
SNIE ROAD NAME = B1 NAME = B2, ETC Record No 1 2 3 4 5 6 7 8 9 10 11 12 Comments LOCATION Site Image: Site Site Site Site Site Site Site Site	0.77																	
Record No 1 2 3 4 5 6 7 8 9 10 11 12 Comments Image: Comment	SILE	ROAD	AD NAME = B1 NAME = B2, ETC															
Record Na 1 2 3 4 5 6 7 8 9 10 11 12 Comments LOCATION Site																		
LOCATION Site Image: Site		Record No.	1	2	3	4	5	6	7	8	9	10	11	12	Comments	S		
Element Element <t< td=""><td>LOCATION</td><td>Site</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>	LOCATION	Site																
WORK ITEM(s) Image: Second		Element																
ABBR'S Elements AB(N/S/E/N) - Abutment (NORTH, SOUTH, EAST, WEST) PR - Pier DK(S/N,S,E,W/C) - Single/ North, South, East, West/ Central Deck Span	WORK ITEI	M(s)																
MAJOR PLANT Image: Constraint of the second of the sec															-			
AJOR PLANT MAJOR PLANT MAJ																		
MAJOR PLANT Image: Constraint of the second sec																		
MAJOR PLANT Image: Constraint of the second sec																		
ABOUR Foreman/LH Image: Company (LH) Image: Company (LH) Carpenter Image: Company (LH) Image: Company (LH) Image: Company (LH) Steel fixer Image: Company (LH) Image: Company (LH) Image: Company (LH) ABBR's Elements AB(N/S/E/W) - Abutment (NORTH, SOUTH, EAST, WEST) PR - Pier DK(S/N,S,E,W/C) - Single/ North, South, East, West/ Central Deck Span SW - Site Works PL - Piling EX(S/H) - Soft/Hard Excavation CS - Caissons RB(B(W/D/P) - Fix Rebar (Base/Walls/Deck/Parapet))	MAJOR PL	ANT																
LABOUR Foreman/LH Image: Carpenter Image: Carpente																		
ABOUR Foreman/LH Image: Carpenter															c			
LABOUR Foreman/LH Image: Carpenter Image: Carpente																		
LABOUR Foreman/LH Image: Carpenter Carpenter Image: Carpenter Image: Carpenter Steel fixer Image: Carpenter Image: Carpenter Labourer Image: Carpenter Image: Carpenter ABBR's Elements AB(N/S/E/W) - Abutment (NORTH, SOUTH, EAST, WEST) PR - Pier DK(S/N,S,E,W/C) - Single/ North, South, East, West/ Central Deck Span SW - Site Works PL - Piling EX(S/H) - Soft/Hard Excavation CS - Caissons RB(B/W/D/P) - Fix Rebar (Base/Walls/Deck/Parapet)																		
Carpenter Steel fixer Steel fixer Steel fixer Labourer Labourer ABBR's Elements AB(N/S/E/W) - Abutment (NORTH, SOUTH, EAST, WEST) PR - Pier DK(S/N,S,E,W/C) - Single/ North, South, East, West/ Central Deck Span SW - Site Works PL - Piling EX(S/H) - Soft/Hard Excavation CS - Caissons RB(B/W/D/P) - Fix Rebar (Base/Walls/Deck/Parapet)	LABOUR	Foreman/LH																
Steel fixer Labourer ABBR's Elements AB(N/S/E/W) - Abutment (NORTH, SOUTH, EAST, WEST) PR - Pier DK(S/N,S,E,W/C) - Single/ North, South, East, West/ Central Deck Span SW - Site Works PL - Piling EXS(S/H) - Soft/Hard Excavation CS - Caissons BBR/S SW - Site Works PL - Piling EX(S/H) - Soft/Hard Excavation CS - Caissons RB(B/W/D/P) - Fix Rebar (Base/Walls/Deck/Parapet)		Carpenter																
ABBR's Elements AB(N/S/E/W) - Abutment (NORTH, SOUTH, EAST, WEST) PR - Pier DK(S/N,S,E,W/C) - Single/ North, South, East, West/ Central Deck Span SW - Site Works PL - Piling EX(S/H) - Soft/Hard Excavation CS - Caissons RB(B/W/D/P) - Fix Rebar (Base/Walls/Deck/Parapet)		Calpenter		-	•													
Labourer ABOUTH ABUL		Steel fixer																
ABBR's Elements AB(N/S/E/W) - Abutment (NORTH, SOUTH, EAST, WEST) PR - Pier DK(S/N,S,E,W/C) - Single/ North, South, East, West/ Central Deck Span SW - Site Works PL - Piling EX(S/H) - Soft/Hard Excavation CS - Caissons RB(B/W/D/P) - Fix Rebar (Base/Walls/Deck/Parapet)		Labourer																
ABBR'S Elements AB(N/S/E/W) - Abutment (NORTH, SOUTH, EAST, WEST) PR - Pier DK(S/N,S,E,W/C) - Single/ North, South, East, West/ Central Deck Span																		
SW - Site Works PL - Piling EX(S/H) - Soft/Hard Excavation CS - Caissons RB(B/W/D/P) - Fix Rebar (Base/Walls/Deck/Parapet)	ABBR's	Elements	AB(N/	S/E/W)	Ab utment	(NORTH	, S OUTH,	EAST, W	EST) P	R - Pier	DK(S/N	,S,E,W/C	- S ingle/	/ North, S	outh, E ast	, W est/ C	entral D e	c k Span
Work items FW(B/W/D/P) - Fix Formwork CP(B/W/D/P) - Concrete Pour BP - cast Bearing Plinth BM - erect Beams HR - fix Handrail		Work items	SW - S FW(B/	Site Works W/D/P) -	s PL - Fix F orm	Piling E work C	X(S/H) - P(B/W/D/	Soft/Hard (P) - Conc	Excavati rete Pour	on CS BP-c	- Caisson cast Beari	s RB(B ng P linth	/W/D/P) BM - e	- Fix Reb rect Bear	ar (Base/N ms HR -	Nalls/Dec fix Handı	k/ P arape ail	t)
Plant PR(1/2) - Piling rig CR(1/2) - Crane BD(1/2) - Bulldozer EX(1/2) - Excavator CT(No off) - Concrete trucks & nos.		Plant	 PR(1/2	2) - Pilir	ngrig C	R(1/2)	- Cr ane	BD(1/2.) - Bulld	ozer E	 X(1/2) -	Excavato	or CT(I	No off) - (Concrete t	rucks & n	 OS.	

VA		RASTR	UCTURE	EREHA	BILITATI	ON AND	IMPRO	/EMENT	PROJE	СТ									
compon	ent:												DATE						
		ET O			ENT 0 C		WORKS												
		EI - 30	JEGRADI	E, PAVEN		SEALING	WURNS						NSPECIOR						
	Record No.	1	2	3	4	5	6	7	8	9	10	Abbreviations							
LOCATION	Road											Road 1= Road 2	=						
	Chainage From											Indicate as appropr	iate						
	To	,										Indicate as appropr	iate						
	Portion											HW(LorR) - Half wi	dth FW -	Full width					
DETAILS	Layer											SG(S/F) - Subgrad BC - Basecourse	e(Stabilised/ PR - Prime	Select Fill SEL(1/2) – SB - S 2) - Seal(1:	sub- b ase st/ 2 nd			
	Material											GR(N/S/C) - Gravel(Natural/Screened/Crushed) CR -							
	Туре											Crushed rock							
	Source	•										CT - Cut BR - B	orrow GP	- Gravel p	it QS -0	Quarry s ite			
	Chainage											Indicate as appropriate							
WORK ITE	M(s)	PM - Plac	ce m aterial	SM - Sp	read m ate	rial ST -	St abilise	FT - Final	trim CP	- Compac	tion	Comments							
												-							
			+									-							
MAJOR PL	ANT	BD(?) - B	ull d ozer (w	ith ref. no.	ST - Sta	abilising " T i	rain" RL(?) - Roller	GD(?) -	Grader S	6P(?) - Sp	ņ							
												~							
			1			+					+	•							

APPENDIX C - Guidance for Additional Sheets

Additional sheets will be required for projects that contain a Supplementary Specification. These should be prepared by the Project Manager at the commencement of the project as soon as the Supplementary Specification has been finalised

[insert document reference eg Supplementary Specification Group 4]											
CHECK S A = Require B = Require C = Laborate D = Measure	SHEET [insert ements Before Phys ments During or Af ory or Field Tests F ement Records	t sheet no and A,B,C or D] sical Works Commence ter Physical Works Required									
Clause	Title	Check	Y/N	Response if N (default is "issue instruction")							
[insert clasue reference	[insert clause title]	[Summarise the requirement to ve verified in the form of a question to which the answer is either 'Ye" or "No"]		[insert any further guidance that inspectors may need]							